



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

2875/MNO

QUOTATION NOTICE

दिनांक: 10/07/2020

To. M/s.....
.....
.....

The sealed quotations are invited for providing and fixing P.P.G.I.sheet on mess no.01 and other misc.work at New C.V hostel from the registered contractor of KGMU.The detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned.Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 17/07/2020
Details of the work as given below-

S.No.	Particulars	Quantity	Unit	Rate
1.	Dismantling of brick work in cement mortar including stacking of material as directed by Engineer-in-charge	0.61	Cum.	
2.	Dismantling cement concrete or granolithic floors, including stacking of dismantling material as per direction by the E/I.	11.11	Sqm.	
3.	Dismantling of old door / windows chaukhats with hold fast & including stacking of dismantled material.directed by the engineer incharge.	1.92	Sqm.	
4.	Dismantling existing old plaster including disposal of refuse as directed by engineer incharge.	9.56	Sqm.	
5.	M-150 class 230mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc.for proper completion of the work.	0.25	Cum.	
6.	M-150 class 120mm thick brick work in 1:4 cement & coarse sand in foundation including supply of all materials, labours and T&P etc.for proper completion of the work.	0.75	Cum.	
7.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	24.21	Sqm.	
8.	P/L PCC 1:6:12 cement, fine sand& 40mm brick ballast.	0.86	Cum.	
9.	P/L Kota stone flooring in 1:4 cement,coarse sand over 25 mm thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the floor including rubbing and polishing complete.	11.11	Sqm.	
10.	P/L cement concrete in 1:2:4 cement ,coarse sand 20mm stone grit.	0.10	Cum.	
11.	Mild steel work for reinforcement in plain cement concrete including binding,bending and cutting complete.	34.85	Kg.	

Cal



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

दिनांक

क्र.सं.	विवरण	मात्रा	इकाई	दिनांक
12.	P/L of R.C.C Platform in 1:2:4 cement, coarse sand & 20mm stone grit.	0.36	Cum.	
13.	P/L 12mm cement plaster in 1:4 cement & fine sand finished with a floating coat of neat cement.	4.32	Sqm.	
14.	Fabrication of M.S structure with M.S angle, M.S square pipe, M.S Square bar for P.P.G.I sheet and R.C.C Cover.	171.45	Kg.	
15.	P/L flamed finish jet black granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including curing and polishing etc. all complete as specified and as direction of the engineer-in-charge.	3.63	Sqm.	
16.	P/F Pre painted galvanised iron sheet Jindal/Tata make ISI sheet 0.45 to .50 mm thick including all materials, labours, and T&P etc complete.	15.34	Sqm.	
17.	Scraping old white or colour wash etc. including disposal of refuse material as directed by Engineer-in-charge.	9.03	Sqm.	
18.	Applying one coat white cement on new surface.	24.21	Sqm.	
19.	Providing and laying white cement based putty of average thickness 1mm of approved band on new surface.	24.21	Sqm.	
20.	Providing and laying cement based white putty of average thickness 0.60mm of approved band and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	9.03	Sqm.	
21.	Distemping with oil bound distemper two coat of approved brand old Surface to give an even shade including all material, labour T&P etc. complete.	47.73	Sqm.	
22.	Painting two coats with Superior synthetic enamel paint on new Surface one coat primer including supply of labour material t&p etc. complete.	5.35	Sqm.	
23.	Painting two coat with Superior synthetic enamel paint on old Surface including supply of labour material t&p etc. complete.	4.34	Sqm.	
24.	Application of two coats apex Ultima paint on outer surface of wall including supply of all materials, labours and T&P etc. for proper completion of the work.	5.08	Sqm.	
25.	Providing Carpenter with helper for repairing of old window.	01	No.	
26.	Providing labour for cleaning of site and collecting of malwa.	04	Nos.	



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003 निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmciindia.edu.

दिनांक:

27. Cartage for disposal of malwa up to away from site.	2.87	Cum.	
---	------	------	--

Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


(Dinesh Kumar Raj)
Executive Engineer

2876-88/M-0
No. of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P. Lucknow.
2. Dr. Sandeep Bhattacharya, Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date... 10/07/2020 To... 17/07/2020
3. Sri Suresh Kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri T.C Yadav, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.


(Dinesh Kumar Raj)
Executive Engineer


Sandeep Kumar