

WORKS DEPARTMENT, KING GEORGE'S MEDICAL
UNIVERSITY U.P, LUCKNOW.

No. 4068.1
M/10

dt. 22/01/18

Quotation Notice

Sub:- P/L of floor tiles below polycarbonate shed at Cardiology department

Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3.30P.m on dated 31.01.18

Sl.No	Particular	Qty	Unit.	Rates
1	P/L of PCC 1;6;12 cement fine sand and 40mm brick ballast	4.80	Cum	
2	Providing and laying pavit floor tiles 300x300mm over 20mm thick cement mortar 1;4 cement and coarse sand including grouting of joints with white cement with matching pigment.	71.00	Sqm.	

Terms & condition


- 1- The quotation should be accepted by Registered Contractor of KGMU.
- 2- The rates should be quoted exclusive G.S.T.
- 3- The work will completed within one week from the date of order.
- 4- The quotation should be reached by Registered post upto date mentioned in quotation.


(Ram Velas Verma)
Executive Engineer

No. 4069-74/M-10
of dt.

Copy for information and necessary action to:

- 1- Registrar, K.G.M.U, Lucknow.
- 2- Finance Officer, K.G.M.U, Lucknow.
- 3- Head of deptt of Lari Cardiology deptt. K.G.M.U, Lucknow.
- 4- Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan KGMU for uploading the quotation Notice in KGMU website.
- 5- Assistant Engineer, Works deptt. K.G.M.U, Lucknow.
- 6- Junior Engineer, Works deptt., K.G.M.U, Lucknow.
- 7- Notice Board.


(Ram Velas Verma)
Executive Engineer