



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003  
निर्माण विभाग (सिविल सेक्शन)

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522-2257539 वेबसाइट : www.kgmcindia.edu.

पत्रांक: 1869 / M-10

दिनांक: 25/6/18

**QUOTATION NOTICE**

To,  
M/s.....  
.....  
.....



The sealed quotations are invited for Renovation of Room (Executive Engineer, Electrical / Mechanical) in Works Department at KGMU from the registered contractor of KGMU. The detail of quotation-notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the undersigned by registered post duly marked on the envelope the number and date of this notice latest by dated 02.07.2018  
Detail of the work as given blow-

Sl.No.	Particulars	Qty.	Unit	Rate
1.	Dismantling windows with chaukhats including hold fast including stacking of dismantled material as directed by Engineer-in-charge.	3.42	Sqm.	
2.	Dismantling existing plaster including disposal of refuse as directed by the Engineer-in-charge with in a distance of 60 metre.	1.09	Sqm.	
3.	Dismantling of old damage cement concrete floor including of dismantled materials as directed by Engineer-in-charge.	17.34	Sqm.	
4.	Dismantling of old damage tiles including of dismantled materials as directed by Engineer-in-charge.	6.06	Sqm.	
5.	P/L P.C.C. 1:6:12 cement , F. sand & 40mm brick balast in foundation.	0.25	Cum.	
6.	M-150 class 120mm thick brick work in 1:4 cement & coarse sand in superstructure including supply of all materials, labours and t&p etc. for proper completion of work.	1.07	Sqm.	
7.	12mm thick cement plaster in 1:6 in single coat on wall with cement and coarse sand including supply of all materials, labours and T&P etc. for proper completion of the work.	13.86	Sqm.	
8.	P/L floor tiles 300x300mm of appd. Quality over 20mm thick cement mortar 1:4 cement and coarse sand.	23.48	Sqm.	
9.	P/L wall tiles 200x300mm of appd. Quality over 20mm thick cement mortar 1:3 cement and coarse sand.	15.47	Sqm.	
10.	S/f of Descon make or equivalent Solid PVC door frames of 65mm x 46mm & shutter 25mm (Solid thick with ribs) Grey/Dark Grey/Black thick mode of Foam PVC sheet including Aluminum hardware, sliding bolt, Handles & hinges.	1.45	Sqm.	
11.	P/L G.I metal false ceiling lay in plain beveled edge global tiles of size 600x600mm and 0.5mm thick with 8mm drop Armstrong make including all labours materials T&P etc. Complete.	15.12	Sqm.	
12.	P/L cement based white putty for making good & smooth surface on new surface.	13.86	Sqm.	
13.	Scraping old white or colour wash etc. including disposal of refuse material as directed by Engineer-in-charge.	32.32	Sqm.	
14.	P/L cement based white putty for making good & smooth surface on old surface.	32.32	Sqm.	

*Handwritten signature*



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग (सिविल सेक्शन)

फोन (कुलसचिव कार्यालय) : 0522-2257540 फेक्स : 0522-2257539 वेबसाइट : www.kgmeindia.edu.

पत्रांक:...../...../.....

दिनांक:...../...../.....

15.	Distemping with oil bound distemper two coat of approved brand old Surface to give an even shade including all material , labour T&P etc. complete.	80.80	Sqm.	
16.	Painting two coat with Superior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	8.98	Sqm.	

Term & Condition

1. G.S.T shall be as per applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.


Yours faithfully


  
(Dinesh Kumar Raj)  
Executive Engineer

No. 1870-1874/M-10 of dt. 25.6.18

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Dr. Sandeep Bhattacharya, Faculty Incharge, Website Administration, Data Center, P.H.I Bhawan, KGMU for Uploading the quotation Notice in KGMU. Website from date.....to.....
3. Sri Suresh Kumar Assistant Engineer, Works deptt. K.G.M.U.U.P. Luck now
4. Sri T.C Yadav, Junior Engineer, Works deptt. K.G.M.U.U.P. Luck now
5. Notice Board.

  
(Dinesh Kumar Raj)  
Executive Engineer

  
Suresh Kumar