



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522-2257539 वेबसाइट : www.kgmcindia.edu.

पत्रांक:

2351/M10

दिनांक: 21/09/17

**QUOTATION NOTICE**

To,

M/s.....

.....

The sealed quotation are invited for Misc. work for P.I.C.U Cancer Unit at Pediatric deptt KGMU as given below. The detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the undersigned duly marked on the envelope the number and date of this notice latest by dated 22/09/17

Sl.No.	Particulars	Qty	Unit	Rate
1	Class 150 brick work 1;4 cement coarse sand in walls for foundation.	0.05	Cum	
2	Class 150 brick work in 1;4 cement coarse sand in walls for foundation.	1.68	Cum	
3	12mm thick plaster 1;4 cement coarse sand on wall.	28.19	Sqm	
4	40mm thickness flooring 1;2;4 cement coarse sand stone aggregate	1.47	Sqm.	
5	P/L PCC work 1;2;4 cement coarse sand stone aggregate.	0.50	Cum	
6	P/L 18mm thick flamed finish granite stone flooring in required design and pattern in base of 1;4 cement coarse sand with joint and white cement slurry admixed including all labour material etc. complete.	0.84	Sqm	
7	P/L vitrified floor tiles size 600x600mm over 20mm thick base of cement mortar 1;4 cement coarse sand including grouting the joint with white cement and matching pigmentic complete.	1.80	Sqm	
8	P/f 1mm thick m.s sheet door with frame of 40x40x6mm angle iron all necessary fitting complete, including applying a priming coat of appd. Steel primer using flat 30x6mm or diagonal braces.	2.12	Sqm	
9	Mild steel work for fabrication of grill.	87.98	Kg.	
10	S/f of anodized al. door heavy 2mm gully glazed made of alu. Door tube size 83.50x44.65mm vertical member.	9.50	Sqm.	
11	S/f of anodized alu. Partly fixed and partly openable window with aluminum section 4x1-3/4x2" window panel and 5mm thick frosted glass including all labour.	1.31	Sqm	
12	S/f of anodized aluminum fixed partition in section 4"x1-3/4"x2.00mm with 5mm thick frosted glass including all labour material t&p etc.	1.31	Sqm	
13	Powder coating/(cost of M.R.F paint coat of approved shade for doors)	9.50	Sqm	
14	S/f of diff. of novapan board in place of plain glass.	4.06	Sqm	
15	S/f of appd. Quality PVC pipe 150mm dia.	8.45	Rmt	



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522-2257539 वेबसाइट : www.kgmcindia.edu.

पत्रांक:...../

दिनांक:...../...../...../

16	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows all complete with 4mm thick glass panes.	0.76	Sqm	
----	--	------	-----	--

Term & Condition

- 1 The rates quoted should be inclusive all taxes as applicable and are FOR at site.
- 2 The work will be completed within given time.
- 3 Quantity can be increase or decrease as per requirements.

Yours faithfully

*Suresh Kumar*  
Assistant Engineer

2352-55/M-10  
No..... of dt.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Dr. Sandeep Bhattacharya, Faculty incharge, Website Administration, Data Center, P.H.I Bhawan, KGMU for uploading the quotation Notice in KGMU Website from dt. 21/09/20 to 27/09/20.
3. Sri Anjani Kumar, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Notice Board.

*Suresh Kumar*  
Assistant Engineer  
*AK*