

**WORKS DEPARTMENT, KING GEORGE'S MEDICAL UNIVERSITY
U.P, LUCKNOW**

No.....1068/M-10

of dt. 21/05/18

Quotation Notice

Sub:- Brick, Plaster, Painting & other Misc Civil work, Corridor, 1st Floor, Deptt. of Ophthalmic , K.G.M.U

Dear sir,

Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3:30 P.m on dated 29/05/18

Sl.No	Particular	Quantity	Unit	Rates
1	Dismantling of old unserviceable flooring.	13.19	Sqm	
2	S/F of Raj Shree P.V.C. door with chaukhet.	6.00	Sqm	
3	Class-150 Brick work 1:4 cement C-Sand in wall for foundation (12c.m. thick)	0.90	Cum	
4	12mm thick plaster 1:3 cement C-Sand in wall.	13.32	Sqm	
5	P/L of appd. quality floor tiles size 300x300mm. Over 20mm. thick base of 1:3 cement coarse sand in complete.	13.19	Sqm	
6	P/L Kajaria or equivalent wall tiles 300x600mm. with water absorption less than 0.08% and conforming to IS:15622 of approved make in all colours and sheds, lied on 20mm. thick cement mortar in 1:4 cement and coarse send including grouting of joints with white cement matching pigment.	1.62	Sqm	
7	P.V.C Connection 24"	03	No	
8	2 Cm(3/4") thick damp proof with course with cement and approved coarse sand 1:2 with and including water proofing materials as ordered by the engineer-in Charge in the proportion as specified by the manufacturers including supply of all material labour and T&P etc required for proper completion of the work including proper curing and shuttering as necessary	13.19	Sqm	
9	P.V.C Band 100mm dia	01	No	
10	S/F PVC p trap 100mm. dia	03	No	
11	S/F of C.P. floor jali 100mm dia.	03	No	
12	P.V.C Pipe 100mm dia	12.10	Rmt	
13	Scraping of colour white wash old surface.	320.10	Sqm	
14	P/L of Birla white putty for making good smooth surface.	320.10	Sqm	
15	Oil bound distemper in two coat.	320.10	Sqm	
16	Enamel painting in two coat	24.36	Sqm.	

Terms & Condition

1. The quotation should be accepted by Registered Contractor of KGMU.
2. The rates should be quoted excluding G.S.T.
3. The work will completed within given time in the work order.
4. The quotation should be reached by Registered post upto date mentioned in quotation.

Yours Faithfully

Ram Velas Verma
(Ram Velas Verma)
Executive Engineer

No. 1069-74/M-10

Date.....

Copy for Information and necessary action to:

1. Registrar, K.G.M.U, U.P. Lucknow
2. Finance Officer, K.G.M.U, U.P. Lucknow
3. Head of Deptt. Ophthalmic, K.G.M.U, U.P. Lucknow
4. Chief Medical Superintendent, K.G.M.U, U.P. Lucknow
5. Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan, KGMU for uploading the quotation Notice in KGMU.
6. Assistant Engineer, Works deptt. K.G.M.U, U.P. Lucknow
7. Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow
8. Notice Board.

Ram Velas Verma
(Ram Velas Verma)
Executive Engineer