

WORKS DEPARTMENT, KING GEORGE'S MEDICAL UNIVERSITY  
U.P, LUCKNOW

No. 2864/M/10

Quotation Notice

of dt. 26/11/17

Sub:- Floor Tile and Wall Tile (Toilet) Old O.P.D First Floor Waiting Area Left Side

Dear sir,


Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3:30 P.m on dated 21/11/17

Sl.No	Particular	Quantity	Unit	Rates
1	P/L of 8 to 10mm thick light vitrified floor tiles 600x600mm size in flooring or skirting laid with adhesive chemical in complete	30.66	Smt	
2	P/L Kajaria or equivalent wall tiles 300x600mm. with water absorption less than 0.08% and conforming to IS:15622 of approved make in all colours and sheds, lied on 20mm. thick cement mortar in 1:4 cement and coarse sand including grouting of joints with white cement matching pigment.	25.63	Smt	

Terms & Condition

1. The Rates should be quoted inclusive all taxes.
2. The work will completed within one week from the date of order.
3. The quotation should be reached by Registered post upto date mentioned in quotation.

Yours Faithfully



(Ram Velas Verma)  
Executive Engineer

2015 7/11/17