



किंग जार्ज चिकित्सा विश्वविद्यालय २०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: -----

6940/M10

दिनांक: 28/03/18

QUOTATION NOTICE

To,

M/s.....

.....

.....

The sealed quotation are invited for P/L Granite on the shelve and painting work in maliquer Biology research lab and cell culture at Biochemisty deptt. KGMU as given below. The detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the undersigned duly marked on the envelope the number and date of this notice latest by 3.30p.m on dated 29/03/18

Sl.No.	Particulars	Quantity	Unit	Rate
1	Class-150 brick work 1:3 cement coarse sand in wall for super structure. 12cm below add extra.	0.80	Cum	
2	12mm thick plaster 1:6 cement coarse sand on wall.	16.50	Sqm	
3	RCC work in slab 1:2:4 cement coarse sand stone aggregate.	0.45	Cum	
4	Mild steel work as for reinforced ment.	45.00	Kg	
5	Mild steel work for fabrication of grill.	210.00	Kg	
6	20mm thick cement plaster 1:4 cement cement coarse sand backing coat 17mm finishing coat 3mm complete.	1.45	Sqm	
7	P/L 18mm thick flamed finish granite stone flooring in required design and pattern, in base of 1:4 cement coarse sand with joint and white cement slurry Admixed including all labour material etc. complete.	6.10	Sqm	
8	Making of oranamental work for granite molding including rubbing and polish.	10.77	Rmt	
9	P/L kajaria or equivalent wall tiles 200x300mm with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and sheds, laid on 12mm thick cement mortar in 1:3 cement coarse sand including grouting of jointes with white cement and matching pigment.	8.10	Sqm	
10	P/F 2mm thick pvc plain sheet for ceiling pitch up to including all labour material t&p etc. complete	22.51	Sqm	
11	Scraping old white or color wash including disposal of refuse as directed by engineer in charge.	160.00	Smt	



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003 निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: -----


दिनांक:.....

12	Providing and laying cement based white putty of average thickness 0.60 mm of approved brand and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	160.00	Smt	
13	Distemping with oil bound distemper two coat of approved brand old Surface to give an even shade including all material, labour T&P etc. complete.	350.00	Smt	
14	Painting two coat with Superior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	75.50	Smt	

Term & Condition

1. G.S.T shall be applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.


Yours faithfully


(Dinesh Kumar Raj)
Executive Engineer

No. 8941-45/M/10 of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Dr. Sandeep Bhattacharya, Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date.....
To 23/03/18 to 09/04/18
3. Sri Anjani Kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri T.C Yadv, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.


(Dinesh Kumar Raj)
Executive Engineer