



किंग जार्ज चिकित्सा विश्वविद्यालय 30प्र0, लखनऊ- 226003  
निर्माण विभाग (सिविल सेक्शन)

फोन (कुलसचिव कार्यालय) : 0522-2257540 फेक्स : 0522-2257539 वेबसाइट : www.kgmcindia.edu.

पत्रांक: 2258/M10

दिनांक: 14/09/17

**QUOTATION NOTICE**

To,

M/s.....  
.....  
.....

The sealed quotation are invited for Water proofing treatment for C.I traps and joints of C.I pipe for Kitchen, toilet & duct in Married block, Gautam Budh Hostel, KGMU. The detail of quotation notice can be seen at website www.kgmcindia.edu and on the notice board of the office of undersigned. Interested parties may submit their quotations to the undersigned duly marked on the envelope the number and date of this notice latest by 3.30p.m on dated 20/09/17

| Sl.No. | Particulars  | Qty                | Unit | Rate |
|--------|--|--------------------|------|------|
| 1      | <p>N-TRAP JOINT ~Series of steps Involved in the Process are as follows:-</p> <ul style="list-style-type: none"><li>• Tile is removed or dismantled</li><li>• Then area under work is uncovered and cleaned by unstable or volatile chemical</li><li>• Cleaned area is repaired by filling/honeycomb covering and chemical putty then treated with 1<sup>st</sup> layer of ISO 117CR.</li><li>• Then 1ft or 1.5ft pipe is set as per the required height and level.</li><li>• After pipe is set 2<sup>nd</sup> Layer of ISO117CR is applied for its covering.</li></ul> <p>After this work is done Tile and drain/jali is fixed and is ready to use after 24 hours.</p>  | 21N-trap           | Each |      |
| 2      | <p>P/S TRAP JOINT:- Series with Orissa pan sheet &amp; European sheet of steps involved in the process are as follows:-</p> <ul style="list-style-type: none"><li>• Commode is removed .</li><li>• Then area under work is cut (1'x1') and uncovered around 6" to 1'5" and cleaned by unstable or volatile chemical.</li><li>• Cleaned area is repaired by filling/honeycomb covering and chemical putty then treated with 1<sup>st</sup> layer of ISO 117CR.</li><li>• Then 4" pipe is set as per the required height After pipe is set 2<sup>nd</sup> layer of ISO 117CR is applied for its covering.</li></ul> <p>After this work is done Tile and commode is fixed and is ready to use after 24 hours.</p> | 09P/s-trap         | Each |      |
| 3      | <p>C,I PIPE JOINT:- Series of steps involved in the process are as follow:-</p> <ul style="list-style-type: none"><li>• Grinding is done on area of work and then it is cleaned.</li><li>• Cleaned area is scratched and leaked joint is covered with 2" web covering.</li><li>• Then around 3mm thick chemical putty is applied.</li><li>• 1<sup>st</sup> Layer of ISO117CR is applied for its covering</li><li>• 4" web covering is done and 2<sup>nd</sup> layer of ISO 117CR is applied.</li></ul>   | 39 C.I pipe joint. | Each |      |

**Term & Condition**

- 1 The rates quoted should be inclusive all taxes applicable and are FOR at site.
- 2 The work will be completed within given time.
- 3 Quantity can be increase or decrease as per requirements.

Yours faithfully

*Suresh Kumar*  
Assistant Engineer

*[Signature]*



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003  
निर्माण विभाग (सिविल सेक्शन)

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522-2257539 वेबसाइट : www.kgmcindia.edu.

पत्रांक: 2259-62/M10

दिनांक: ..... / ..... / .....

No. .... / ..... of dt. ....

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Dr. Sandeep Bhattacharya, Faculty Incharge, Website Administration, Data Center, P.H.I Bhawan, KGMU for Uploading the quotation Notice in KGMU. Website from date 19/09/12 to 20/09/12
3. Sri T.C Yadav, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Notice Board.

Suresh Kumar  
Assistant Engineer

V. S. S.