



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग (सिविल सेक्शन)

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522-2257539 वेबसाइट : www.kgmcindia.edu.

पत्रांक: 5136 / M10

27/10/18

QUOTATION NOTICE


To,

M/s.....
.....
.....

The sealed quotations are invited for Construction of Toilet at Second Floor in Plastic Surgery Department KGMU from the registered contractor of KGMU. The detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 23/11/18..
Detail of the work as given blow-

Sl.No.	Particulars	Qty	Unit	Rate
1.	Dismantling existing old plaster including disposal of refuse as directed by Engineer-in-charge .	21.73	Sqm.	
2.	S/F cinder light weight in sunken portion of toilet including all materials, labours T&P etc. complete .	0.38	Cuft.	
3.	P/L Brick coba 12mm thick laid with M-150 class brick bat, coba 7.5cm thick with gap of 15mm to each other over 20mm thick base of cement mortar in 1:4 cement & coarse sand withwater proofing compound including gola 30cm higher.Juction and corner should be rounded brick ballast,cement &coarse sand.	7.63	Sqm.	
4.	P/L P.C.C. 1:6:12 cement , F. sand & 40mm brick balast in foundation.	0.61	Cum.	
5.	C.C. 1:2:4 cement, coarse sand & 20mm grit stone for flooring.	0.31	Cum.	
6.	S/F Pvc pipe 100mm dia ISI Marked.	2.70	Rmt.	
7.	S/F pipe 50mm dia ISI Marked.	3.97	Rmt.	
8.	S/F Pvc Nahani Trap 100mm dia ISI Marked.	4.00	Nos.	
9.	S/F Pvc Plain bend 100mm dia ISI Marked.	4.00	Nos.	
10.	M-150 class 230 mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc.for proper completion of the work.	0.68	Cum.	
11.	M-150 class 120 mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc.for proper completion of the work.	0.56	Cum.	
12.	S/F GI pipe 15mm dia with fittings 'B' class	8.14	Rmt.	
13.	S/F GI pipe 20mm dia with fittings 'B' class	5.70	Rmt.	
14.	12mm thick cement plaster in 1:6 in single coat on wall with cement and coarse sand including supply of all materials, labours and T&P etc.for proper completion of the work.	28.21	Sqm.	
15.	P/L wall tiles 300x450mm of appd. Quality over 20mm thick cement mortar 1:3 cement and coarse sand.	29.85	Sqm.	
16.	P/L wall tileS 300x600mm of appd. Quality over 20mm thick cement mortar 1:3 cement and coarse sand.	2.63	Sqm.	

Urf



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग (सिविल सेक्शन)

फोन (कुलसचिव कार्यालय) : 0522-2257540 फ़ैक्स : 0522-2257539 वेबसाइट : www.kgmcindia.edu.

पत्रांक:...../.....

17.	P/L granite border tiles 3" wide of appd. Quality over 20mm thick cement mortar 1:4 cement and coarse sand.	0.37	Sqm.	
18.	P/L floor tiles 300x300mm of appd. Quality over 20mm thick cement mortar 1:4 cement and coarse sand.	8.01	Sqm.	
19.	Applying one coat white cement on new surface.	28.21	Sqm.	
20.	Scraping old white or colour wash etc.including disposal of refuse material as directed by Engineer-in-charge.	28.03	Sqm.	
21.	P/L cement based putty for making good & smooth surface on new surface.	28.21	Sqm.	
22.	P/L cement based putty for making good & smooth surface on old surface.	28.03	Sqm.	
23.	Distemping with oil bound distemper two coat and one coat primer of approved brand and required shade on decorated wall surfaces togive an even shade including all materials, lobours T&P etc. complete.	56.24	Sqm.	

Term & Condition

- 1 G.S.T & Labour Cess shall be applicable as per rules .
- 2 The work will be completed within given time.
- 3 Quantity can be increase or decrease as per requirements.
- 4 Conditional quotations are liable to be rejected.
- 5 The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully



(Dinesh Kumar Raj)
Executive Engineer




5137-41/M/1e
No...../..... of dt. 27/10/18

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Dr. Sandeep Bhattacharya, Faculty Incharge, Website Administration, Data Center, P.H.I Bhawan, KGMU for Uploading the quotation Notice in KGMU. Website from date 27/10/18 to 23/11/18.
3. Sri Suresh Kumar Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri T.C Yadav, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.


(Dinesh Kumar Raj)
Executive Engineer