

**WORKS DEPARTMENT, KING GEORGE'S MEDICAL
UNIVERSITY U.P, LUCKNOW.**

No.....4075.....
M/Mo

dt.22/01/18

Quotation Notice

Sub:- Repair and other misc. work for room No.1,2,3,4,5,6 in G.F for Midweifery building.

Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3.30P.m on dated 31.01.18

Sl.No	Particular	Qty	Unit.	Rates
1	Dismantling of old brick work in cement mortar including stacking of material.	7.05	Cum	
2	Dismantling of old existing plaster including disposal of refuse material as directed by Engineer-in-charge .	35.00	Sqm.	
3	Dismantling of old unserviceable cement flooring.	8.38	Sqm.	
4	P/L of birla white putty for making good and smooth surface	402.00	Sqm.	
5	Distempering with oil bound distemper two coat of approved brand on decorated wall surfaces to give an even shade including all materials, labours T&P etc. complete .	681.24	Sqm.	
6	Painting 2coat with superior synthetic enamel paint. on previously painted old surface over 10 cm width or grith.	318.87	Sqm.	
7	Enamel painting on old fans.	17.00	Nos.	
8	12mm plaster 1;4 cement coarse sand on wall.	39.50	Sqm.	
9	PCC flooring 1;2;4 cement coarse sand stone aggregate 1" thick including base conc. Complete.	9.38	Sqm.	

Terms & condition

- 1- The quotation should be accepted by Registered Contractor of KGMU.
- 2- The rates should be quoted excluding G.S.T.
- 3- The work will completed within one week from the date of order.
- 4- The quotation should be reached by Registered post upto date mentioned in quotation.

4076-82/M/Mo
No. / of dt.

Copy for information and necessary action to:

- 1- Registrar, K.G.M.U, Lucknow.
- 2- Finance Officer, K.G.M.U, Lucknow.
- 3- Chief Proctor. K.G.M.U, Lucknow.
- 4- Principal, Nursing, K.G.M.U, Lucknow.
- 5- Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan KGMU for uploading the quotation Notice in KGMU website.
- 6- Assistant Engineer/Junior Engineer, Works deptt. K.G.M.U, Lucknow.
- 7- Notice Board.

Ram Velas Verma
(Ram Velas Verma)
Executive Engineer

Arjun
Arjun

Ram Velas Verma
(Ram Velas Verma)
Executive Engineer

Arjun
Arjun



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग (सिविल सेक्शन)

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522-2257539 वेबसाइट : www.kgmcindia.edu.

पत्रांक: 4020/M-10

दिनांक: 19/11/18

QUOTATION NOTICE

To,
M/s.....
.....
.....

The sealed quotation are invited for Providing & fixing Cattle Catcher at entrance of PHC Sarojini nagar as given below. The detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the undersigned duly marked on the envelope the number and date of this notice latest by dated 27/11/18

Sl.No.	Particulars	Qty	Unit	Rate
1	Excavation in ordinary soil including lift upto 1.5 m. lead upto 50m and dressing and rammings of surface.	3.60	Cum.	
2	P/L P.C.C. 1:6:12 cement, F. sand & 40mm brick balast in foundation.	0.48	Cum.	
3	M-150 class brick work in 1:4 cement & coarse sand in foundation including supply of all materials, labours and T&P etc.for proper completion of the work.	1.40	Cum.	
4	M-150 class brick work in 1:4 cement & coarse sand in superstructure including supply of all materials, labours and T&P etc.for proper completion of the work.	0.35	Cum.	
5	P/L C.C. 1:2:4 cement, coarse sand & 20mm grit stone for slab.	1.50	Cum.	
6	P/L of 12mm cement plaster in 1:6 in single coat on wall with cement and coarse sand including supply of all materials, labours and T&P etc.for proper completion of the work.	15.00	Sqm.	
7	Fabrication of M.S. (I section 110x225mm)work including welding where necessary and also including supply of all materials,labours T&P for proper completion of the work.	288.00	Kg.	
8	S/f G.I. pipe 80mm dia.	44.00	Rmt.	

Term & Condition

- 1 G.S.T shall be as per applicable.
- 2 The work will be completed within given time.
- 3 Quantity can be increase or decrease as per requirements.

Yours faithfully

(Dinesh Kumar Raj)
Executive Engineer

4021-25/M-10
No..... of dt.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Dr. Sandeep Bhattacharya, Faculty Incharge, Website Administration, Data Center, P.H.I Bhawan, KGMU for Uploading the quotation Notice in KGMU. Website from date 19/11/18 to 27/11/18.
3. Sri Suresh Kumar Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri T.C Yadav, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.

(Dinesh Kumar Raj)
Executive Engineer

WORKS DEPARTMENT, KING GEORGE'S MEDICAL
UNIVERSITY U.P, LUCKNOW.

No. 4068.1
M/10

dt. 22/01/18

Quotation Notice

Sub:- P/L of floor tiles below polycarbonate shed at Cardiology department

Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3.30P.m on dated 31.01.18

Sl.No	Particular	Qty	Unit.	Rates
1	P/L of PCC 1;6;12 cement fine sand and 40mm brick ballast	4.80	Cum	
2	Providing and laying pavit floor tiles 300x300mm over 20mm thick cement mortar 1;4 cement and coarse sand including grouting of joints with white cement with matching pigment.	71.00	Sqm.	

Terms & condition


- 1- The quotation should be accepted by Registered Contractor of KGMU.
- 2- The rates should be quoted exclusive G.S.T.
- 3- The work will completed within one week from the date of order.
- 4- The quotation should be reached by Registered post upto date mentioned in quotation.


(Ram Velas Verma)
Executive Engineer

No. 4069-74/M-10
of dt.

Copy for information and necessary action to:

- 1- Registrar, K.G.M.U, Lucknow.
- 2- Finance Officer, K.G.M.U, Lucknow.
- 3- Head of deptt of Lari Cardiology deptt. K.G.M.U, Lucknow.
- 4- Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan KGMU for uploading the quotation Notice in KGMU website.
- 5- Assistant Engineer, Works deptt. K.G.M.U, Lucknow.
- 6- Junior Engineer, Works deptt., K.G.M.U, Lucknow.
- 7- Notice Board.


(Ram Velas Verma)
Executive Engineer

**WORKS DEPARTMENT, KING GEORGE'S MEDICAL
UNIVERSITY U.P, LUCKNOW.**

No. 4047 / M10

dt. 22/01/18

Quotation Notice


Sub:- Outer(front portion) painting of Urology department

Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3.30P.m on dated 30/01/18

Sl.No	Particular	Qty	Unit.	Rates
1	Scraping old white or colour wash including disposal of refuse material as directed by Engineer-in-charge with a distance of 60 met.	220.40	Sqm.	
2	P/L of birla white putty for making good and smooth surface	220.40	Sqm.	
3	Distempering with oil bound distemper two coat of approved brand on decorated wall surfaces to give an even shade including all materials, labours T&P etc. complete .	22.92	Sqm.	
4	Application of two coats apex ultima paint on outer surface of wall including supply of all materials, labours and T&P etc. for proper completion of the work.	906.00	Sqm.	
5	Painting 2coat with superior synthetic enamel paint on previously painted old surface over 10 cm width or grith.	20.41	Sqm.	

Terms & condition


- 1- The quotation should be accepted by Registered Contractor of KGMU.
- 2- The rates should be quoted exclusive G.S.T.
- 3- The work will completed within one week from the date of order.
- 4- The quotation should be reached by Registered post upto date mentioned in quotation.


(Ram Velas Verma)
Executive Engineer

No. 4048-53 / M10
of dt.

Copy for information and necessary action to:

- 1- Registrar, K.G.M.U, Lucknow.
- 2- Finance Officer, K.G.M.U, Lucknow.
- 3- Head of deptt of Urology deptt. K.G.M.U, Lucknow.
- 4- Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan KGMU for uploading the quotation Notice in KGMU website.
- 5- Assistant Engineer, Works deptt. K.G.M.U, Lucknow.
- 6- Junior Engineer, Works deptt., K.G.M.U, Lucknow.
- 7- Notice Board.


(Ram Velas Verma)
Executive Engineer

**WORKS DEPARTMENT, KING GEORGE'S MEDICAL
UNIVERSITY U.P, LUCKNOW.**

No. *4040* *M/10*

dt *20/01/18*

Quotation Notice

Sub:- P/L Red Lakha stone on platform in Pathology and other misc. work in OPD of Respiratory Medicine department

Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3.30P.m on dated *30/01/18*

Sl.No	Particular	Qty	Unit.	Rates
1.	M-150 class 120mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc.for proper completion of the work.	0.17	Cum	
2	12mm cement plaster in 1:6 in single coat of wall with cement and coarse sand including supply of all materials, labours and T&P etc.for proper completion of the work.	1.26	Sqm.	
3	Scraping old white or colour wash including disposal of refuse material as directed by Engineer-in-charge with a distanse as distance of 60 met.	90.00	Sqm.	
4	P/L of birla white putty for making good and smooth surface	90.00	Sqm.	
5	Distempering with oil bound distemper two coat of approved brand on decorated wall surfaces togive an even shade including all materials, lobours T&P etc. complete .	326.41	Sqm.	
6	Painting 2coat with supirior synthetic enamel paint. on previously painted old surface over 10 cm width or grith.	113.45	Sqm.	
7	P/L of approved Lakha red granite in 1:3 cement coarse sand in flooring including grouting and polishing all complete.	7.91	Sqm.	
8	L/c Moulding on granite stone including polishing to edge.	17.08	Rmt.	
9	Providing and fixing fly proof galvanized M.S. wire gauge to windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm With 2nd class teak wood beading 62X19 mm complete.	20.75	Sqm.	

Terms & condition

- 1- The quotation should be accepted by Registered Contractor of KGMU.
- 2- The rates should be quoted exclusive G.S.T.
- 3- The work will completed within one week from the date of order.
- 4- The quotation should be reached by Registered post upto date mentioned in quotation.

Ram Velas Verma
(Ram Velas Verma)
Executive Engineer

No. *4041-46/M/10* of dt.

Copy for information and necessary action to:

- 1- Registrar, K.G.M.U, Lucknow.
- 2- Finance Officer, K.G.M.U, Lucknow.
- 3- Head of deptt of Respiratory Medicine deptt. K.G.M.U, Lucknow.
- 4- Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan KGMU for uploading the quotation Notice in KGMU website.
- 5- Assistant Engineer, Works deptt. K.G.M.U, Lucknow.
- 6- Junior Engineer, Works deptt., K.G.M.U, Lucknow.
- 7- Notice Board.

Ram Velas Verma
(Ram Velas Verma)
Executive Engineer

WORKS DEPARTMENT, KING GEORGE'S MEDICAL UNIVERSITY
U.P, LUCKNOW

No. U061/M/10

Quotation Notice

of dt. 22/01/18

Sub:- Painting & other Misc Civil work, Two Car Parking Garages (Old Building, FODS)

Dear sir,


Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3:30 P.m on dated 22/01/18

Sl.No	Particular	Quantity	Unit	Rates
1	P/L of 1:6:12 Cement fine sand brick aggregate.	4.08	Cmt	
2	P/L of Pavit tile over 20mm. thickness base of 1:4 cement for sand in wall/floor.	39.26	Sqm	
3	C.C. work in 1:2:4 Cement C-Sand stone aggregate.	0.44	Cmt	
4	Scraping of colour white wash old surface.	140.83	Smt	
5	P/L of Birla white putty for making good smooth surface.	140.83	Smt	
6	Oil bound distemper in two coat.	100.93	Smt.	
7	Application of two coats Apex. Altima paint of Approved Brand on old Surface Given an even Shade including supply of all material, labour T&P as required for proper completion of work	56.90	Smt	
8	Supply and fixing 6mm thick gray corrugated asbestos cement sheet roofing in position including supply of all materials, labour and T&P etc. required for proper completion of work.	6.90	Sqm	
9	S/F P.V.C Pipe 150mm dia	2.44	Rmt	

Terms & Condition

1. The quotation should be accepted by Registered Contractor of KGMU.
2. The rates should be quoted exclusive G.S.T.
3. The work will completed within one week from the date of order.
4. The quotation should be reached by Registered post upto date mentioned in quotation.

Yours Faithfully




(Ram Velas Verma)
Executive Engineer

No. U062-68/M/10

Date 22/01/18

Copy for Information and necessary action to:

1. Registrar, K.G.M.U, U.P. Lucknow
2. Finance Officer, K.G.M.U, U.P. Lucknow
3. Superintendent, Dental K.G.M.U, U.P. Lucknow
4. Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan, KGMU for Uploading the quotation Notice in KGMU.
5. Assistant Engineer, Works deptt. K.G.M.U, U.P. Lucknow
6. Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow
7. Notice Board.



(Ram Velas Verma)
Executive Engineer