

**WORKS DEPARTMENT, KING GEORGE'S MEDICAL UNIVERSITY
U.P, LUCKNOW**

No..... U.S.73/
M/10

of dt. 30/09/18

Quotation Notice

Sub:- Misc civil Toilet Renovation & Sainitary work, Resident Room Ground Floor Faculty Q.M.H.

Dear sir,

Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3:30 P.m on dated.....

Sl.N o	Particular	Quantity	Unit	Rates
1	Dismantling of old unserviceable flooring/Kota stone	3.54	Sqm	
2	40mm thick flooring 1:2:4 cement C-sand stone Aggregate of with floating coat of neat cement.	0.18	Sqm	
3	Earth work in Excavation in trenches for foundation in ordinary soil.	15.55	Cum	
4	P/L P.C.C. 1:6:12 cement, fine sand and 40mm brick ballast in foundation.	0.35	Cum	
5	C.C. work in 1:2:4 Cement C-Sand stone aggregate.	0.14	Cum	
6	Class-150 Brick work 230mm thick wall in 1:4 cement and coarse sand in superstructure.	0.21	Cum	
7	P/L 20mm cement plaster in 1:3 cement, coarse sand with floating coat of neat cement.	1.79	Sqm	
8	Mild Steel work 10/12 mm dia as for reinforced ment	6.00	Kg	
9	P.V.C Pipe 100mm dia	36.60	Rmt	
10	P.V.C. Elbow 100mm dia	07	Nos	
11	P.V.C. Tee 100mm dia	06	Nos	
12	P.V.C.Socket	36	Nos	
13	P/L of appd.quality Pavit floor tiles size 300x300mm. over 20mm. thick base of 1:3 cement coarse sand in complete.	3.54	Sqm	
14	S/F C.P. extension piece 75mm long.	02	Nos	
15	S/f C.P short body bib cock 15mm dia.	03	Nos	
16	S/F of C.P head shower with arm.	02	No	
17	Commod Sheat with cover (Cera Make)	01	Nos	
18	S/f P.V.C low level flushing cistern 10 liter capacity with long bend and internal fitting complete.	01	Nos	
19	S/f C.P. jaali 100mm dia.	03	Nos	
20	S/f of C.P. towel rod 750x20mm of approved quality	01	Nos	
21	S/F looking mirror glass with bracket	01	No	
22	S/f C.P. angle valve 15mm dia	03	No	
23	S/F Sink Mixer bib cock	01	No	
24	S/F of C.P soap dish	01	No	
25	S/F West Pipe 32mm	01	No	
26	S/F P.V.C. Connection 24"	02	No	
27	Z-Spray	02	No	
28	Cartage of malva up to away from side.	4.20	Cum	
29	Scraping of colour white wash old surface.	221.43	Sqm	
30	P/L of Birla white putty for making good smooth surface.	221.43	Sqm	
31	Oil bound distemper in two coat.	221.43	Sqm	

of Aluminium fixed partition with 4"x1 3/4"x2mm. Aluminium section with 5mm. plane/frosted glass.	1.08	Sqm	
--	------	-----	--

Condition

1. The quotation should be accepted by Registered Contractor of KGMU.
2. The rates should be quoted excluding G.S.T. & Labuor Cess.
3. The work will completed within given time in the work order.
4. The quotation should be reached by Registered post upto date mentioned in quotation.

Yours Faithfully

Ram Velas Verma

(Ram Velas Verma)
Executive Engineer

Ram Velas Verma

No. *4574-79/M-10*

Date.....

Copy for Information and necessary action to:

1. Registrar, K.G.M.U, U.P. Lucknow
2. Finance Officer, K.G.M.U, U.P. Lucknow
3. Head of Q.M.H., K.G.M.U, U.P. Lucknow
4. Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan,
KGMU for uploading the quotation Notice in KGMU.
5. Assistant Engineer, Works deptt. K.G.M.U, U.P. Lucknow
6. Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow
7. Notice Board.

Ram Velas Verma

(Ram Velas Verma)
Executive Engineer

Ram Velas Verma