

**WORKS DEPARTMENT, KING GEORGE'S MEDICAL UNIVERSITY
U.P. LUCKNOW**

of dt. 20/11/19

No. 27/19

5826/M-16

Quotation Notice

Sub:- Misc Civil Sanitary work, False Ceiling Repairing, Door Repairing & other work, Deptt of Q.M.H., K.G.M.U. U.P., Lucknow

Dear sir,

Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3:30 P.m on dated 23/12/19

Sl.No	Particular	Quantity	Unit	Rates
1	S/f of P.V.C. short body bib cock 15mm dia make of prayag.	06	No	
2	S/F P.V.C. Bib Cock Long Body	02	No	
3	S/f of C.P. Pillar cock 15mm dia.	04	No	
4	S/f orrisa pan 580mm dia.	02	Nos	
5	S/f of P.V.C. Angle valve 15mm dia.	03	No	
6	S/f of P.V.C. waste pipe for wash basin/sink	12	No	
7	S/f of C.P. brass waste jali for wash basin	05	No	
8	S/f of Bracket with fashner	01	Pair	
9	S/F of P.V.C. Connection 600mm long.	01	No	
10	S/f wash basin 22"x16" with PVC connection, pillar cock and bracket complete.	01	Nos	
11	S/f of 10 lit P.V.C. low down cistern for appd. quality in completed.	03	No	
12	S/f of C.P. Elbow action bib cock 15mm dia.	01	No	
13	S/f of P.V.C. ball cock completed 15mm dia.	01	No	
14	P.V.C. Elbow 100mm dia	02	Nos	
15	S/f of P.V.C. Long band for Orissa pan.	01	No	
16	S/f of C.P.V.C. Brass Tee 20mm dia.	01	No	
17	S/F of P.V.C. Pipe 100mm. dia	13.30	Rmt	
18	S/f of P.V.C. Pipe 50mm dia.	2.40	Rmt	
19	S/f of P.V.C. Pipe 150mm dia with fitting.	5.20	Rmt	
20	S/f of G.I. Long screw 15mm dia.	02	No	
21	S/f of G.I. Union 50mm dia.	02	No	
22	S/f of G.I. Union 15mm dia.	02	No	
23	S/F of G.I. socket 15mm dia.	03	No	
24	S/F of G.I. Elbow 15mm dia	02	No	
25	S/f of P.V.C. Cistern Handle	01	No	
26	S/F of Aluminium door stoppers.	05	No	
27	S/f of 5mm thick glass with putten	6.37	Sqm	
28	Rubber Beading	5.10	Rmt.	
29	S/f Citkani 8"	02	No	
30	Alluminium Door/Partition Repair Labour charge complete etc.	25.22	Sqm	
31	S/f of Nova Pan Board in duct window Iron Frame.	0.94	Sqm	
32	C.C. work in 1:2:4 cement C-Sand stone aggregate.	0.05	Cum	
33	12mm thick plaster 1:3 cement C-Sand in wall.	10.03	Sqm	
34	Mild Steel work 10/12mm dia as for reinforcement.	10.50	Kg	
35	P/L of 20mm. approved quality of Red Lakha granite slab/stone in rise of steps skirting dodo walls and pliiars, laid of 10mm. thick base jointed with cement slurry including colouming all labour material T & P etc. upto the proper competition of the work as per direction of Engineer-in-charge.	0.78	Sqm	
36	Providing and laying Vitrified tiles in floor with different sized(thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade laid with cement based high ploymer modified quick set tile adhesive(water based) conforming to IS:15477, in average 6mm. thickness, including grouting of joints (Payment for grouting of joints to be made separately) (Size of tile 600x600mm)	11.15	Sqm	
37	P/L Kajaria or equivalent wall tiles 300x600mm. with water absorption less than 0.08% and conforming to IS:15622 of approved make in all colours and sheds, lied on 20mm. thick cement mortar in 1:4 cement and coarse sand including grouting of joints with white cement matching pigment.	0.67	Sqm	
38	P/L 12mm thick cement plaster in 1:4 on ceiling with cement and coarse sand including supply of all material labour and T&P etc. for proper completion of the work.	11.27	Sqm	
39	P/L metal False Ceiling of appd. Quality with G.I. Section including all labour material all Complete as per direction of Engineer-in-charge.	9.66	Sqm	

Scraping of colour white wash old surface.	17.10	Sqm	
P/L of Birla white putty for making good smooth surface.	27.13	Sqm	
Oil bound distemper in two coat.	44.38	Sqm	
False Ceiling Repair labour material complete etc.	11.27	Sqm.	

Terms & Condition

1. The quotation should be accepted by Registered Contractor of KGMU.
2. The rates should be quoted excluding G.S.T. & Labuor Cess.
3. The work will completed within given time in the work order.
4. The quotation should be reached by Registered post upto date mentioned in quotation

Yours Faithfully

(Ram Velas Verma)
Executive Engineer

No.

5827-32/M/10 Date 20/11/19

Copy for Information and necessary action to:

1. Registrar, K.G.M.U, U.P. Lucknow
2. Finance Officer, K.G.M.U, U.P. Lucknow
3. Head Deptt. of Q.M.H., K.G.M.U, U.P. Lucknow
4. Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan, KGMU for uploading the quotation Notice in KGMU.
5. Assistant Engineer, Works deptt. K.G.M.U, U.P. Lucknow
6. Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow
7. Notice Board.

(Ram Velas Verma)
Executive Engineer