

**WORKS DEPARTMENT, KING GEORGE'S MEDICAL  
UNIVERSITY U.P, LUCKNOW.**

No. 6215 / M-10

dt. 13/03/18

**Quotation Notice**

Sub:- Repairing and other mise work for corridors, toilet, corner room at ground floor in Midwifry building .


Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3.30P.m on dated 20/03/18

Sl.No	Particular	Qty	Unit.	Rates
1	Scraping of old surface.	155.00	Sqm	
2	P/L a coat of birla white putty for making the surface smooth.	160.00	Sqm	
3	Oil bound distempering in two coats on old surface	670.33	Sqm	
4	Enamel painting in two coats on old surface	196.92	Sqm	
5	PCC works for flooring 1:2:4 cement coarse sand stone aggregade of 1 inch thickness complete.	14.24	Sqm	
6	S/F galvanized wire guage mesh with beading	5.29	Sqm	
7	S/F of hollow PVC door I/C welding machine, welders, electrodes & MS hinges on old angle iron frame	1.50	Sqm	
8	Mild steel work for fabrication of iron chaukhat 40X40 5mm angle iron .	16.41	kg	
9	S/F of 32 mm thick single leaf flush door with iron oxide fitting.	1.43	Sqm	
10	S/F of approved quality of WC Orissa-pan made of CERA size 500mm dia complete.	3	No	
11	S/F of approved quality of European seat complete.	1	No	
12	S/F of 10 litre pvc low down cistern complete	1	No	
13	S/F of PVC pipe 4 inch dia	1.60	Rmt	
14	S/F of 100 mm dia C.I P trape	3	No	
15	S/F of PVC Nahani trape	1	No	
16	S/F of 15mm dia PVC bib cock Prayag make.	3	No	
17	S/F of CP alpha zet spray	1	No	
18	S/F of 15mm dia 2 way angle wall	1	No	
19	S/F of 4 inch dia CP jali	2	No	
20	Plumber with helper for shifting the old G.I pipe line in veranda.	1	No	
21	S/F of PVC connection	1	No	
22	S/F of wooden frame 3"x1" section with panel of size 0.45x0.55 of 25mm thickness panel door with iron oxidized fitting	2	No	
23	Lobour charges for cleaning old bushes , malwa ,trees roots , etc near by the building .	8	No	
24	S/F of 4 mm thick ply on door & window.	0.91	Smt	
25	Dismantling of old existing broken floor I/C base concrete .	12.25	Smt	

26	Dismantling of old existing plaster.	10.00	Sqm	
27	12mm thick plaster in 1:4 cement coarse sand on wall .	14.50	Sqm	

Terms & condition

- 1-The rates should be quoted excluding G.S.T.
- 2-The work will completed within one week from the date of order.
- 3-The quotation should be accepted by Registered Contractor of KGMU.
- 4-The quotation should be reached by Registered post upto date mentioned in quotation.




(Ram Velas Verma)  
Executive Engineer

No. 6216-21/ML of dt.

Copy for information and necessary action to:

- 1-Registrar, K.G.M.U, Lucknow.
- 2-Finance Officer, K.G.M.U, Lucknow.
- 3-Dr.Sandeep Bhattacharya website Administration Finance & Conatct P.H.I Bhawan ,K.G.M.U  
Uploading the quotation Notice in K.G.M.U.
- 4.Incharge midwifery KGMU.Lucknow.
- 5-Assistant Engineer, Works deptt. K.G.M.U, Lucknow.
- 6-Junior Engineer, Works deptt., K.G.M.U, Lucknow.
- 7-Notice Board.



(Ram Velas Verma)  
Executive Engineer