



03-07-2020

**किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003**  
**निर्माण विभाग**

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: 2690/AN/10

दिनांक:

21/07/2020

**QUOTATION NOTICE**

To,

M/s.....  
.....  
.....

The sealed quotations are invited for Repairing and Water-proofing of toilet blocks at 1st and 2nd floor of New Nehru hostel building. The details of quotation notice can be seen at website [www.kgmcindia.edu](http://www.kgmcindia.edu) and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 29/07/2020.

Details of work as given below:-

S.N o.	Particulars	Quantity	Unit	Rate
1.	Water proofing treatment for N Trap of C.I/PVC pipe with resin based water proofing chemical including fiber glass matt and fine powder. Applying chemical coating around trap in three layers up to 3to 4mm and 150mm long. Filling of chemical around trap in cutting area of floor should be 50mm thick and also including removing of existing cp jali from trap and refixing complete.	19	Nos.	
2.	Water proofing treatment for P Trap of C.I/PVC pipe with resin based water proofing chemical including fiber glass matt and fine powder. Applying chemical coating around trap in three layers up to 3to 4mm and 150mm long. Filling of chemical around trap in cutting area of floor should be 50mm thick and also including removing and refixing of existing pan.	08	Nos.	
3.	Water proofing treatment for joints of C.I/PVC pipe with resin based water proofing chemical including fiber glass matt and fine powder width of chemical coating on joint not less than 250mm on any dia of pipe. Applying chemical coating on joint in three layers up to 3to 4mm thick and also including filling of gap between collar and pipe with resin based putty including fiber glass matt.	14	Nos.	
4.	P/L cement concrete in 1:2:4 cement ,coarse sand 20mm stone grit.	0.71	Cum.	
5.	P/L vitrified floor tiles in 600x600mm (thickness to be specified by the manufacture ) with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and sheds , laid on 20mm thick cement mortar in 1:4 cement coarse sand including grouting of jointes with white cement and matching pigment etc. complete.	11.88	Sqm.	
6.	S/F Orrisa pan 580 mm with C.I. trap.	04	Nos.	

**Terms & Conditions**

1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

(Dinesh Kumar Raj)  
Executive Engineer