

**WORKS DEPARTMENT, KING GEORGE'S MEDICAL UNIVERSITY U.P,  
LUCKNOW.**

No. 4061 / M-10

of dt. 22/11/18

**Quotation Notice**

Name of work:- Misc. work between old V.L. Hostel and chhatra chhatravas.

The sealed quotations are invited for Misc. work between old V.L. Hostel and chhatra chhatravas as per specifications given below. Interested parties may submit their quotations to the undersigned duly marked on the envelope the number and date of this notice latest by 3.30p.m on dated 30/11/18...

S.N	Particular	Quantity	Unit	Rates
1	Dismantling cement concrete floor including stacking of material as directed by Engineer-in-charge .	340.38	Sqm.	
2	Earth work in excavation in ordinary soil including lift upto 1.5 m. lead upto 50m and dressing of sides and rammings of bottom .	49.84	Cum.	
3	P/L P.C.C. 1:6:12 cement , F. sand & 40mm brick balast in foundation.	6.65	Cum.	
4	C.C. 1:2:4 cement , coarse sand & 20mm grit stone for flooring .	0.99	Cum.	
5	Providing M-150 brick ballast 40mm gauge.	8.17	Cum.	
6	M-150 class 230mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc.for proper completion of the work.	1.26	Cum.	
7	M-150 class 120mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc.for proper completion of the work.	0.60	Cum.	
8	12mm cement plaster in 1:6 in single coat of wall with cement and coarse sand including supply of all materials, labours and T&P etc.for proper completion of the work.	5.03	Sqm.	
9	S/F PVC pipe 100mm dia.	5.50	Rmt.	
10	Providing and laying RCC cover in 1:2:4 cement, coarse sand and 20mm stone grit including cost of all material ,labour,T&P complete.	0.16	Cum.	
11	Mild steel work for reinforcement in plain concrete work including supply of all material and its binding complete.	25.43	Kg.	
12	S/f M.S. pipe 40mm dia with grouting for badmintalcourt.	9.60	Rmt.	
13	Cartage for disposal of malwa upto 6.00Km.from site.	63.48	Cum.	

**Terms & condition**

1. The rates should be quoted exclusive G.S.T.
2. The work will completed within one week from the date of order.
3. The quotation should be reached by Registered post upto date mentioned in quotation.

Yours faithfully

*Ram Velas Verma*

(Ram Velas Verma)  
Executive Engineer

*Vel*

No. 4062-66 / M-10  
of dt.

1. Registrar, K.G.M.U, Lucknow.
2. Finance Officer, K.G.M.U U.P, Lucknow.
3. Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan, KGMU for Uploading the quotation Notice in KGMU.
4. Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow.
5. Junior Engineer , Works deptt. K.G.M.U. U.P, Lucknow.
6. Notice Board.

*Ram Velas Verma*

(Ram Velas Verma)  
Executive Engineer

*Vel*