

किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003 निर्माण विभाग

फोन (कुलसचिव कार्यालय): 0522-2257540 बेवसाइट: www.kgmu.org

प्रयांकः	 1588/		
9 7197	 1/10		

QUOTATION NOTICE

	•••
18/11	
10/1/2023	•

Го,	The second secon
9	M/s

The sealed quotations are invited for miscellaneous repair and painting work in 4 nos of faculty chambers at General surgery department the detail of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 2.3/11/2020.2. Details of the work as given below-

Sl.No.	Particulars	Qty.	Unit	Rate
1.	Dismantling existing old plaster including disposal of refuse as directed by Engineer-in-charge.	30.54	Sqm	
2.	P/L wall tiles 300x600mm with water absorption less then 0.08% and conferming to IS: 15622 of approved make in all colours and sheds, laid on 12mm thick cement mortar in 1:3 cement coarse sand including grouting of joints with white cement and matching pigment.	20.07	Sqm	
3.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	10.47	Sqm	
4.	Scraping old white or colour wash etc. including disposal of refuse material as directed by engineer in charge.	55.07	Sqm	
5.	Providing and laying white cement basede putty of average thickness 0.60mm of approved brand on old painted wall surface surface.	55.07	Sqm	(*)
6.	Distempering with oil bound disemper two coat of approved brand on old surface to give an even shade including all material, labour T&P etc. complete	98.64	Sqm	
7.	Painting two coats with supirior synthetic enamel paint in old surface including supply of labour material t&p etc. complete.	19.51	Sqm	
8.	P/F anodised aluminum work for partitions with extruded built up standard tubular section Z section and other section of approved make comforming to IS: 733 and is: 1285 fixing with dash fasteners of required dia size including necessary fittings up the gaps at juctions I.E at top, bottom, and sides with required EPDM	27.75	kg	18.
9.	S/F ACP sheet in palce of plain glass	2.18	Sqm	
10.	Providing & fixing glass panes 4 mm thick with putty and glazing clips in steel doors, windows, clerestory windows, all complete	2.74	Sqm	
11.	S/F C.P health faucet including with hose pipe 1.50 m long.	03	Nos	\$ 1 m
12.	S/F door closer for appd quality godrej or equvalent	05	Nos	
13.	P/F Pvc wall panneling using board profile including all complete.	14.11	Sqm	
14.	Providing labour (unskilled) for cleaning of site and collecting malwa	02	Nos	

Terms & Conditions.

- 1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
- 2. The work will be completed within given time.
- 3. Quantity can be increase or decrease as per requirements.





किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ— 226003 निर्माण विभाग

SINCERTY SERVICE SACRIFICE	फोन (कुलसचिव कार्यालय) : 0522-2257540 बेवसाइट : www.kgmu.org	7.	
Tallas		टिगांक:	Carolida (1800 - 18
पत्राक:	ional quotations are liable to be rejected	14414	

5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

(Dinesh Kumar Raj) (Suresh Kumar) Executive Engineer Superintendent Engineer

Copy for information and necessary action to:-

Registrar, King George's Medical University U.P, Lucknow.

Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date. 161.11.1.2023. To 23.1.1.1.2023. Sri Suresh kumar, Executive Engineer, Works deptt. K.G.M.U.U.P.Lucknow.

4. Sri T.C Yadav, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow

5. Sri Poshit Roy, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow

6. Notice Board.

(Suresh Kumar) (Dinesh Kumar Raj) Executive Engineer Superintendent Engineer