

**WORKS DEPARTMENT, KING GEORGE'S MEDICAL UNIVERSITY
U.P, LUCKNOW.**

No. 2052 / M10

of dt. 16/08/17

Quotation Notice

Sub:- Misc. work between old V.L. Hostel and chhatra chhatravas.

Dear sir,

Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3.30P.m on dated 24/08/17.

Sl. No	Particular	Quantity	Unit	Rates
1	Dismantling cement concrete floor including stacking of material as directed by Engineer-in-charge .	340.38	Sqm.	
2	Earth work in excavation in ordinary soil including lift upto 1.5 m. lead upto 50m and dressing of sides and rammings of bottom .	49.84	Cum.	
3	P/L P.C.C. 1:6:12 cement , F. sand & 40mm brick balast in foundation.	6.65	Cum.	
4	C.C. 1:2:4 cement , coarse sand & 20mm grit stone for flooring .	0.99	Cum.	
5	Providing M-150 brick ballast 40mm gauge.	8.17	Cum.	
6	M-150 class 230mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc.for proper completion of the work.	1.26	Cum.	
7	M-150 class 120mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc.for proper completion of the work.	0.60	Cum.	
8	12mm cement plaster in 1:6 in single coat of wall with cement and coarse sand including supply of all materials, labours and T&P etc.for proper completion of the work.	5.03	Sqm.	
9	S/F PVC pipe 100mm dia.	5.50	Rmt.	
10	Providing and laying RCC cover in 1:2:4 cement, coarse sand and 20mm stone grit including cost of all material ,labour,T&P complete.	0.16	Cum.	
11	Mild steel work for reinforcement in plain concrete work including supply of all material and its binding complete.	25.43	Kg.	
12	S/f M.S. pipe 40mm dia with grouting for badmintalcourt.	9.60	Rmt.	
13	Cartage for disposal of malwa upto 6.00Km.from site.	63.48	Cum.	

Terms & condition

- 1- The rates should be quoted inclusive all taxes.
- 2- The work will completed within one week from the date of order.
- 3- The quotation should be reached by Registered post upto date mentioned in quotation

Yours faithfully

/
(Ram Velas Verma)
Executive Engineer

No. 2053-58 / M10

of dt.

Copy for information and necessary action to:

- 1 Registrar, K.G.M.U, Lucknow.
- 2 Finance Officer, K.G.M.U U.P, Lucknow.
- 3 Provost D.K.Hostel & Chhatra-Chhatravas K.G.M.U.U.P, Lucknow.
- 4 Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan, KGMU for Uploading the quotation Notice in KGMU. Website.
- 5 Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow.
- 6 Junior Engineer , Works deptt. K.G.M.U. U.P, Lucknow.
- 7 Notice Board.

/
(Ram Velas Verma)
Executive Engineer