



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग (सिविल सेक्शन)

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522-2257539 वेबसाइट : www.kgmcindia.edu.

पत्रांक: 2253/1

M/10

दिनांक: 14/09/12

To,

QUOTATION NOTICE

M/s.....
.....
.....

The sealed quotation are invited for Construction of kuda ghar in Gautam Budh hostel KGMU as given below. The detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the undersigned duly marked on the envelope the number and date of this notice latest by dated 20/09/12.

Sl.No.	Particulars	Qty	Unit	Rate
1	Earth work in foundation including dressing and ramming of surface.	3.10	Cum	
2	P/L PCC 1;6;12 cement, fine sand and 40mm brick ballast.	4.04	Cum	
3	M-150 class 120mm thick brick work in 1;4 cement & coarse sand in foundation including supply of all materials, labours and t&p etc. for proper completion of work.	1.48	cum.	
4	M-150 class 230mm thick brick work in 1;4 cement & coarse sand in superstructure including supply of all materials, labours and t&p etc. for proper completion of work.	2.97	cum.	
5	M-150 class 120mm thick brick work in 1;4 cement & coarse sand in superstructure including supply of all materials, labours and t&p etc. for proper completion of work.	2.30	cum.	
6	12mm cement plaster in 1;4 in single coat on wall with cement and coarse sand including supply of all materials, labours and t&p etc. for proper completion of the work.	55.00	sqm.	
7	P/L kota stone flooring over 20mm thick cement mortar in 1;4 cement and coarse sand.	39.10	Sqm.	
8	P/L birla white putty for making good & smooth surface.	85.00	sqm.	
9	Application of two coats apex paint with one coat white cement on outer surface of wall including supply of all materials, labours and t&p etc. for proper completion of work.	85.00	sqm.	
10	L/c for repairing of old interlocking tiles			
11	Fabrication of m.s grill for transformer.	40.00	Sqm	
12	Providing labour for cleaning of site and collecting malwa.	25.00	Kg.	
	Term & Condition	4.00	No.	

Term & Condition

- 1 The rates quoted should be inclusive all taxes as applicable and are FOR at site.
- 2 The work will be completed within given time.
- 3 Quantity can be increase or decrease as per requirements.

No. 2254-57/M/10 of dt.

Yours faithfully
Suresh Kumar
Assistant Engineer

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Dr. Sandeep Bhattacharya, Faculty incharge, Website Administration, Data Center, P.H.I Bhawan, KGMU for uploading the quotation Notice in KGMU Website from dt. 14/09/12 to 20/09/12
3. Sri T.C Yadav, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Notice Board.

Suresh Kumar
Assistant Engineer

Cal
J.E.