

**WORKS DEPARTMENT. KING GEORGE'S MEDICAL
UNIVERSITY U.P, LUCKNOW.**

No.....*2420/1*
NY10

dt.*28/09/17*

QUOTATION NOTICE

To,

M/s.....
.....
.....

The sealed quotations are invited for Painting and repairing of Dr. Santosh kumar and Dr. S.K. Verma room and other misc. work in Respiratory medicine department . as per specifications given below. Interested parties may submit their quotations to the undersigned duly marked on the envelope the number and date of this notice latest by 3.30p.m on dated *27.11.17*.....


Sl.No.	Particulars	Qty	Unit	Rate
1	M-150 class 230mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc.for proper completion of the work.	1.63	Cum	
2	Dismantling existing old plaster including disposal of refuse as directed by Engineer-in-charge .	58.24	Sqm.	
3	P/L 12mm cement plaster in 1:6 in single coat on wall with cement and coarse sand including supply of all materials, labours and T&P etc.for proper completion of the work.	58.24	Sqm.	
4	12mm cement plaster in 1:6 in single coat of ceiling with cement and coarse sand including supply of all materials, labours and T&P etc.for proper completion of the work.	9.90	Sqm.	
5	P/L 12mm cement plaster in 1:4 in single coat with cement and coarse sand including floating coat with neat cement .	2.45	Sqm.	
6	P/L cement concrete flooring 40 mm thick in 1:2:4 cement, coarse sand and 20mm stone grit with floating coat with neat cement .	5.38	Sqm.	
7	P/L C.C. 1:2:4 cement , coarse sand & 20mm grit stone for slab.	4.02	Cum.	
8	P/L P.C.C. 1:6:12 cement , F. sand & 40mm brick balast in foundation.	0.21	Cum.	
9	P/L RCC cover in 1;2:4 cement, coarse sand and 20mm grit stone.	0.41	cum.	
10	Mild steel work for reinforcement in plain concrete work.	59.01	Kg.	
11	Scraping old white or colour wash including disposal of refuse material as directed by Engineer-in-charge with a distanse as distance of 60 met.	193.67	Sqm.	

12	P/L of birla white putty for making good and	251.91	Sqm.	
13	Distempering with oil bound distemper two coat of approved brand on decorated wall surfaces to give an even shade including all materials, labours T&P etc. complete .	251.91	Sqm.	
14	Painting 2coat with superior synthetic enamel paint on previously painted old surface over 10 cm width or grith.	77.76	Sqm.	

Terms & condition

- 1- The rates quoted should be inclusive all taxes applicable and are FOR at site.
- 2- The work will completed within one week from the date of order.
- 3- The quotation should be reached by Registered post upto date mentioned in quotation


Yours faithfully



Assistant Engineer

No. 2421-25/MTC / of dt.

- 1 Registrar, K.G.M.U, Lucknow.
- 2 Finance Officer, K.G.M.U U.P, Lucknow.
- 3 Head of deptt. Of Respiratory Medicine deptt. KGMU, U.P Lucknow.
- 4 Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan, KGMU for Uploading the quotation Notice in KGMU.
- 5 Junior Engineer , Works deptt. K.G.M.U. U.P, Lucknow.
- 6 Notice Board.



Assistant Engineer

