

किंग जार्ज चिकित्सा विश्वविद्यालय लखनऊ, लखनऊ- 226003

निर्माण विभाग (सिविल सेक्शन)

फोन (कुलसचिव कार्यालय) : 0522-2257540 फॅक्स : 0522-2257539 वेबसाइट : www.kgmcindia.edu.

पत्रांक

3721

M-10

9/09/18

QUOTATION NOTICE

To,

M/s.....


.....

.....

The sealed quotations are invited for Construction of Toilet for Faculty of Human Organ Transplant at ground floor in shabdi hospital phase-I KGMU from the registered contractor of KGMU. The detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the undersigned by registered post duly marked on the envelope the number and date of this notice latest by dated

Detail of the work as given blow-

Sl.No.	Particulars	Qty	Unit	Rate
1.	Dismantling old damage tiles flooring including disposal of refuse as directed by Engineer in-charge.	15.98	Sqm.	
2.	Dismantling old damage cement concrete flooring including disposal of refuse as directed by Engineer-in-charge	0.20	Cum.	
3.	P/L P.C.C. 1:6:12 cement, F. sand & 40mm brick balast in foundation.	0.32	Cum.	
4.	S/P of C.I pipe 100mm dia HEPCO make.	18.15	Rmt.	
5.	C.C. 1:2:4 cement, coarse sand & 20mm grit stone for flooring.	0.64	Cum.	
6.	M-150 class brick work in 1:4 cement & coarse sand in foundation including supply of all materials, labours and T&P etc for proper completion of the work.	0.08	Cum.	
7.	M-150 class 120mm thick brick work in 1:3 cement & coarse sand in super structure including supply of all materials, labours and T&P etc for proper completion of the work.	0.50	Cum.	
8.	P/L RCC work in 1:2:4 cement, coarse sand and 20mm grit stone for lintel including necessary centering and shuttering & also including supply of all materials, labours and T&P etc complete.	0.02	Cum.	
9.	Mild steel work for reinforcement in plain concrete work including cutting bending and binding complete.	6.71	Kg.	
10.	12mm cement plaster in 1:6 in single coat on wall with cement and coarse sand including supply of all materials, labours and T&P etc for proper completion of the work.	2.39	Sqm.	
11.	P/L wall tiles 300x600mm of appd. Quality over 20mm thick cement mortar 1:3 cement and coarse sand.	9.15	Sqm.	
12.	P/L floor tiles 600x600mm of appd. Quality over 20mm thick cement mortar 1:4 cement and coarse sand.	15.98	Sqm.	
13.	P/L of 20 mm thick granite strips in broken corners of wall tiles over 20mm thick base of 1:3 cement coarse sand and joint with white cement slurry including rubbing and polishing complete.	0.84	Sqm.	
14.	Providing edge moulding to 18mm thick Granite stone counters, vanities etc. including machinepolishing to edge give high gloss finish etc complete.	1.22	Rmt.	



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग (सिविल सेक्शन)

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522-2257539 वेबसाइट : www.kgmcindia.edu.


पत्र क्र. /

15.	Applying one coat white cement on new surface.	2.39	Sqrs.
16.	Scraping old white or colour wash etc.including disposal of refuse material as directed by Engineer-in-charge.	16.22	Sqm.
17.	P/L Cement based putty for making good and smooth surface on old surface.	16.22	Sqm.
18.	P/L Cement based putty for making good and smooth surface on new surface.	2.39	Sqm.
19.	Distempering with oil bound distemper two coat of approved brand on decorated wall surfaces to give an even shade including all materials, labours T&P etc. complete.	18.61	Sqm.
20.	L/c for repairing of old False ceiling.	15.81	Sqm.
21.	L/c for Repairing of Old Aluminium door.	2.16	Sqm.
22.	S/F G.I pipe 15mm dia with fitting.	4.00	Rm.
23.	S/F C.I Nahani trap 100mm dia F EPCO make.	1.00	Nos.
24.	S/F of C.I plain bend 100mm dia H EPCO make.	1.00	Nos.
25.	S/F of C.I collar 100mm dia H EPCO make.	3.00	Nos.
26.	S/F European type white glazed earthen ware W.C.pan seat 580mm dia with bakelite white seat cover.	1.00	Nos.
27.	S/F C.P health faucet with c.p lead 1.5m.for appd. quality.	1.00	Nos.
28.	S/F 10 Lit PVC low down cistern for appd. Quality in completed.	1.00	Nos.
29.	S/F wash basin 630x450mm with pedestal concord type cera make.	1.00	Nos.
30.	S/F PVC waste pipe 32mm dia 600m long.	1.00	Nos.
31.	S/F C.P extension piece 1.5x100mm long.	3.00	Nos.
32.	S/F C.P pillar cock 15mm dia make of Cera.	1.00	Nos.
33.	S/F C.P angle valve 15mm dia make prayag.	2.00	Nos.
34.	S/F of PVC connection 450mm long Prayag make	2.00	Nos.
35.	S/F C.P two way bib cock 15mm dia make prayag.	1.00	Nos.


Term & Condition

1. G.S.T & Labour Cess shall be applicable as per rules.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


(Dinesh Kumar Raj)
Executive Engineer


E



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग (सिविल सेक्शन)

फोन (कुलकर्णीय कार्यालय) : 0522-2257530 फैक्स : 0522-2257539 वेबसाइट : www.kgmcindia.edu.

क्रमांक.....

No. 3722-26/M/10
of dt.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Dr. Sandeep Bhattacharya, Faculty Incharge, Website Administration, Data Center, P.H.I Bhawan, KGMU for Uploading the quotation Notice in KGMU Website from date 11.09.18 to 12.09.18
3. Sri Anjali Kumar Assistant Engineer, Works deptt. K.G.M.U.U.P. Lucknow
4. Sri T.C. Yadav, Junior Engineer, Works deptt. K.G.M.U.U.P. Lucknow
5. Notice Board.

(Dipankar Kumar Raj)
Executive Engineer

[Signature]
E

QUOTATION NOTICE