

**WORKS DEPARTMENT, KING GEORGE'S MEDICAL
UNIVERSITY U.P, LUCKNOW.**

No. 1735 / M/10

dt. 20/07/17

Quotation Notice

Sub: Misc. work for Providing Police Chauki Space at Lari Cardiology department.

Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3.30P.m on dated 28/7/17

Sl.No	Particular	Qty	Unit.	Rates
1	Class 150 brick work 1:4 cement coarse sand 12cm thick wall in super structure.	2.30	Cum.	
2	P/L 12mm thick cement Plaster in 1:6 cement and coarse sand on wall surface.	23.00	Sqm.	
3	Providing anodized Alu. Door & Window of tubular section with dash fashner including all material labour t&p etc complete.	118.00	Kg.	
4	S/f glazing 5.5mm thick on alu. Door and windows with EPDM rubber complete.	4.80	Sqm.	
5	Providing and fixing 12mm thick laminated particle board.	4.28	Sqm.	
6	Providing and fixing anodised alu. Grill with mosquito wire gauge.	4.32	Sqm	
7	Scraping of old white /colour wash including disposal of refuse material.	55.00	Sqm.	
8	P/L birla white putty one coat.	121.71	Sqm	
9	Distempering of two coats oil bound distemper including all material labours t&p etc.	81.81	Sqm.	
10	Application of two coats apex Ultima paint.	39.90	sqm	

Terms & condition

- 1- The rates should be quoted inclusive all taxes.
- 2- The work will completed within one week from the date of order.
- 3- The quotation should be reached by Registered post upto date mentioned in quotation.


(Ram Velas Verma)
Executive Engineer

No. 1736-41 / M/10
of dt.