

**WORKS DEPARTMENT, KING GEORGE'S MEDICAL  
UNIVERSITY U.P, LUCKNOW.**

No... 6441 /  
M-10

dt. 20/03/18

Quotation Notice

Name of work- Misc. work for Chamber of Neera Kohli in Radiodiagnosis Department KGMU.


The sealed quotations are invited for Misc. work for Chamber of Neera Kohli in Radiodiagnosis Department KGMU. Geriatric Department KGMU as per specifications given below. Interested parties may submit their quotations to the undersigned duly marked on the envelope the number and date of this notice latest by 3.30p.m on dated .....

Sl.No.	Particulars	Qty	Unit	Rate
1	Dismantling existing old plaster including disposal of refuse as directed by Engineer-in-charge.	38.96	Sqm.	
2	12mm cement plaster in 1:4 in single coat of ceiling with cement and coarse sand including supply of all materials, labours and t&petc. for proper completion of work.	3.75	Sqm.	
3	P/L wall tiles 300x600mm of appd. Quality over 20mm thick cement mortar 1;4 cement and coarse sand.	20.00	Sqm.	
4	S/f anodized aluminium fixed partition in section 4"x1,3/4" with 5mm thick plain glass.	0.53	Sqm.	
5	Diff. of novapan board in place of plain glass.	0.33	Sqm.	
6	S/f of aluminium door stopper for door shutter.	1.00	Nos.	
7	Repairing of false ceiling including all required material labour t&p etc. complete .	1.44	Sqm.	
8	S/f of P.V.C connection pipe 450mm long.	3.00	Nos.	
9	S/f of CP one way angle valve 15 mm dia ISI marked.	3.00	Nos.	
10	S/f of C.P jet with C.P lead. Jaguar make.	1.00	Nos.	
11	S/f of European seat white glazed earthen ware with backlite seat cover complete.	1.00	Nos.	
12	S/f of C.P Mixer with hand hand spray appd. Quality materials.	1.00	Nos.	
13	PVC long body bib cock 15mm (prayag make)	1.00	Nos.	
14	S/F C.P jaali 100mm dia ISI Marked.	1.00	Nos.	
15	S/f of C.P soap dish ISI Marked.	1.00	Nos.	
16	S/f of C.P towel ring ISI Marked.	1.00	Nos.	
17	S/f G.I pipe 15mm dia with fitting 'B' class	2.30	Rmt.	
18	S/f PVC cistern 10litre. capacity with internal fitting compete ISI marked.	1.00	Nos.	
19	S/f wash basin white glazed 550x400 mm. size complete with pillar cock, bucket, waste jali, waste pipe, P.V.C. connection etc.	1.00	Nos.	

Terms & condition

1. The quotation should be accepted by Registered Contractor of KGMU.
2. The rates should be quoted excluding G.S.T.
3. The work will completed within one week from the date of order.
4. The quotation should be reached by Registered post upto date mentioned in quotation.


Yours faithfully



(Ram Velas Verma)  
Executive Engineer

No. 442-46/MF10 of dt.

1. Registrar, K.G.M.U, Lucknow.
2. Finance Officer, K.G.M.U U.P, Lucknow.
3. Head of deptt of Radiodiagnosis deptt. K.G.M.U.U.P. Lucknow.
4. Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan, KGMU for  
Uploading the quotation Notice in KGMU.
5. Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow.
6. Junior Engineer , Works deptt. K.G.M.U. U.P, Lucknow.
7. Notice Board.



(Ram Velas Verma)  
Executive Engineer