

162

**WORKS DEPARTMENT, KING GEORGE'S MEDICAL
UNIVERSITY U.P, LUCKNOW.**

No. U313 / 13/2/18

dt. 06/02/18

Quotation Notice

Name of work- P/F wall tiles in Verandah near Dr. RAS Kushwaha Chamber in Respiratory Medicine Department KGMU.


The sealed quotations are invited for P/F wall tiles in verandah near Dr. RAS Kushwaha Chamber in Respiratory Medicine Department KGMU as per specifications given below. Interested parties may submit their quotations to the undersigned duly marked on the envelope the number and date of this notice latest by 3.30p.m on dated 13/02/18...

Sl.No.	Particulars	Qty	Unit	Rate
1	Dismantling existing old plaster including disposal of refuse as directed by Engineer-in-charge.	69.24	Sqm.	
2	12mm cement plaster in 1:6 in single coat on wall with cement and coarse sand including supply of all materials ,labours and T&P etc.proper completion of work.	33.20	Sqm.	
3	P/L wall tiles 300x600mm. size of approved quality ISI marked over 20mm. thick cement mortar in 1:4 cement & coarse sand.	36.04	Sqm.	
4	Providing and laying red lakha granite in skirting over 20mm thick cement mortar in 1:4 cement and coarse sand.	5.90	Sqm.	
5	P/L border tiles 3" wide of appd. Quality over 20mm thick cement mortar 1:4 cement and coarse sand.	1.61	Sqm.	
6	L/C for moulding on granite edge .	5.97	Sqm.	
7	P/L of cement based white putty for making good and smooth surface on new surface.	33.20	Sqm.	
8	Scraping old white or colour wash including disposal of refuse material as directed by Engineer-in-charge with a distance as distance of 60 met.	59.08	Sqm.	
9	P/L of cement based white putty for making good and smooth surface on old surface.	59.08	Sqm.	
10	Distempering with oil bound distemper two coat of approved brand on decorated wall surfaces to give an even shade including all materials, labours T&P etc. complete .	59.08	Sqm.	
11	Painting 2coat with superior synthetic enamel paint on previously painted old surface over 10 cm width or grith.	59.08	Sqm.	
12	S/f masquito proof wire gauge.	1.94	Sqm.	

Terms & condition

1. The quotation should be accepted by Registered Contractor of KGMU.
2. The rates should be quoted exclusive G.S.T.
3. The work will completed within one week from the date of order.
4. The quotation should be reached by Registered post upto date mentioned in quotation.

Yours faithfully


(Ram Velas Verma)
Executive Engineer

E

