

**WORKS DEPARTMENT, KING GEORGE'S MEDICAL UNIVERSITY
U.P, LUCKNOW**

No... 3887 / M/10

of dt. 15/01/18

Quotation Notice

Sub:- Renovation of Kitchen, Tile, Painting & Other Misc civil work, Deptt. of Old Dental
(Dean Office)

Dear sir,

Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3:30 P.m on dated 24/01/18


SLN	Particular	Quantity	Unit	Rates
1	Class-150 Brick work 1:4cement C-Sand in wall Superstructure below 12cm thick.	0.35	Cmt	
2	R.C.C. work in slab 1:1½:3 cement C-Sand stone aggregate.	0.22	Cmt	
3	Mild steel work 6/32mm. dia as for reinforcement.	25.500	Kg	
4	P/L of 20mm. approved quality of Red Lakha granite slab/stone in rise of steps skirting dodo walls and pliiars, laid of 10mm. thick base jointed with cement slurry including colouring all labour material T & P etc. upto the proper competition of the work as per dirction of Engineer-in-charge.	3.40	Sqm	
5	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS:733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing/panelling, C.P brass/stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge.(Glazing, panelling and dash fasteners to be paid for separately):	1.74	Sqm	
6	Providing and laying Vitrified tiles in floor with different sized(thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade laid with cement based high ploymer modified quick set tile adhesive(water based) conforming to IS:15477, in average 6mm. thickness, including grouting of joints (Payment for grouting of joints to be made separately) (Size of tile 600x600mm)	14.70	Sqm	
7	P/L Kajaria or equavalent wall tiles 300x600mm. with water absorption less than 0.08% and conforming to	20.30	Sqm	

	IS:15622 of approved make in all colours and sheds, lied on 20mm. thick cement mortar in 1:4 cement and coarse sand including grouting of joints with white cement matching pigment.			
8	Scraping of colour white wash old surface.	42.15	Sqm	
9	P/L of Birla white putty for making good smooth surface.	42.15	Sqm	
10	Oil bound distemper in two coat.	42.15	Sqm	
11	S/F Steel sink 24x18x8 complete bracket waste jali, waste pipe.	1	No	

Terms & Condition

1. The quotation should be accepted by Registered Contractor of KGMU.
2. The rates should be quoted exclusive G.S.T.
3. The work will completed within one week from the date of order.
4. The quotation should be reached by Registered post upto date mentioned in quotation.

Yours Faithfully



(Ram Velas Verma)
Executive Engineer

No. 3888-93/M-10

Date.....

Copy for Information and necessary action to:

1. Registrar, K.G.M.U, U.P. Lucknow
2. Finance Officer, K.G.M.U, U.P. Lucknow
3. Dean, Dental, K.G.M.U, U.P. Lucknow
4. Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan, KGMU for Uploading the quotation Notice in KGMU.
5. Assistant Engineer, Works deptt. K.G.M.U, U.P. Lucknow
6. Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow
7. Notice Board.



(Ram Velas Verma)
Executive Engineer