



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003  
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: \_\_\_\_\_

4026/M-10

दिनांक: 17/09/18

**QUOTATION NOTICE**

The sealed quotation are invited for Water proofing treatment on the roof and other misc. work at Gautam Buddha hostel KGMU from the registered contractor of KGMU the detail of quotation notice can be seen at website [www.kgmcindia.edu](http://www.kgmcindia.edu) and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the undersigned by registered post duly marked on the envelope the number and date of this notice latest by dated 24/09/18  
Detail of the works as given below-

Sl.No.	Particulars	Quantity	Unit	Rate
1.	M-150 class 230mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc. for proper completion of the work.	1.14	Cum	
2.	Fabrication of M.S. truss/grill for window including supply of all materials, labours and T&P etc.for proper completion of the work.	80.00	Kg	
3.	P/L of A.C 6mm thick corrugated sheets (As per IS:14871) roofing up to any pitch and fixing with polymer coated J, or L hooks.bolt and nuts 8mm dia.	19.22	Sqm	
4.	P/L Water proofing treatment on roof with resin based water proofing chemical with fiber matting including grinding of surface for making rough then applying first coat of resin chemical and after applying first coat laying of fiber matting over coated surface then applying one more coat of resin chemical over fiber matting thickness of final coat is 4 to 5mm thick and final layer is finishing with matching pigment or colour if necessary and including all labour matereal, t&p etc. complet.	493.08	Sqft	
5	Providing and laying cement based white putty of average thickness 0.60mm of approved band and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	75.25	Sqm	
6	Application of two coats Ultima apex paint on outer surface of wall including supply of all materials, labours and T&P etc.for proper completion of the work.	75.25	Sqm	
7	Labour charge for cleaning of roof and other misc. work.	2.00	Nos	

**Term & Condition**

1. G.S.T shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reson.