

**WORKS DEPARTMENT, KING GEORGE'S MEDICAL  
UNIVERSITY U.P, LUCKNOW.**

No. .... 3614/1 / M10

dt. 27/12/17

**Quotation Notice**


**Sub:- Painting and repairing of Dr. Santosh kumar and Dr. S.K. Verma room and other misc. work in Respiratory medicine department**

Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3.30P.m on dated 23/11/18

Sl.No	Particular	Qty	Unit.	Rates
1	M-150 class 230mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc.for proper completion of the work.	1.63	Cum	
2	Dismantling existing old plaster including disposal of refuse as directed by Engineer-in-charge .	58.24	Sqm.	
3	P/L 12mm cement plaster in 1:6 in single coat on wall with cement and coarse sand including supply of all materials, labours and T&P etc.for proper completion of the work.	58.24	Sqm.	
4	12mm cement plaster in 1:6 in single coat of ceiling with cement and coarse sand including supply of all materials, labours and T&P etc.for proper completion of the work.	9.90	Sqm.	
5	P/L 12mm cement plaster in 1:4 in single coat with cement and coarse sand including floating coat with neat cement .	2.45	Sqm.	
6	P/L cement concrete flooring 40 mm thick in 1:2:4 cement, coarse sand and 20mm stone grit with floating coat with neat cement .	5.38	Sqm.	
7	P/L C.C. 1:2:4 cement , coarse sand & 20mm grit stone for slab.	3.50	Cum.	
8	P/L P.C.C. 1:6:12 cement , F. sand & 40mm brick balast in foundation.	0.21	Cum.	
9	P/L RCC cover in 1:2:4 cement, coarse sand and 20mm grit stone.	0.41	cum.	
10	Mild steel work for reinforcement in plain concrete work.	59.01	Kg.	
11	Scraping old white or colour wash including disposal of refuse material as directed by Engineer-in-charge with a distance as distance of 60 met.	193.67	Sqm.	
12	P/L of birla white putty for making good and smooth surface	251.91	Sqm.	
13	Distemping with oil bound distemper two coat of approved brand on decorated wall surfaces togive an even shade including all materials. lobours T&P etc. complete .	251.91	Sqm.	
14	Painting 2coat with supirior synthetic enamel paint on previously painted old surface over 10 cm width or grith.	77.76	Sqm.	

**Terms & condition**


- 1- The quotation should be accepted by Registered Contractor of KGMU.
- 2- The rates should be quoted exclusive G.S.T.
- 3- The work will completed within one week from the date of order.
- 4- The quotation should be reached by Registered post upto date mentioned in quotation.

  
(Ram Velas Verma)  
Executive Engineer

No. 3615-20/M10 / 1 of dt.

Copy for information and necessary action to:

- 1- Registrar, K.G.M.U, Lucknow.
- 2- Finance Officer, K.G.M.U, Lucknow.
- 3- Head of deptt of Respiratory Medicine deptt. K.G.M.U, Lucknow.
- 4- ~~Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan KGMU for uploading the quotation Notice in KGMU website.~~
- 5- Assistant Engineer, Works deptt. K.G.M.U, Lucknow.
- 6- Junior Engineer, Works deptt., K.G.M.U, Lucknow.
- 7- Notice Board.

  
(Ram Velas Verma)  
Executive Engineer

