

**WORKS DEPARTMENT, KING GEORGE'S MEDICAL
UNIVERSITY U.P, LUCKNOW.**

No. 4384 / M/10

dt. 08/02/18

QUOTATION NOTICE

Name of work- Misc. work for Providing Police Chauki Space at Lari Cardiology Department.

The sealed quotations are invited for Misc. work for Providing Police Chauki Space at Lari Cardiology Department. as per specifications given below. Interested parties may submit their quotations to the undersigned duly marked on the envelope the number and date of this notice latest by 3.30p.m on dated 18/02/18.....

Sl.No.	Particulars	Qty	Unit	Rate
1	M-150 class 120mm thick brick work in 1:4 cement & coarse sand including supply of all materials, labours and T&P etc.for proper completion of the work.	2.30	Cum.	
2	12mm cement plaster in 1;4 in single coat of wall with cement and coarse sand including supply of all materials,labours and t&p etc. for proper completion of work.	23.00	Sqm.	
3	S/f of 2-1/2"x1-3/4" section of aluminum doors with 5mm thick plane glass including all labour material t&p.	5.69	Sqm.	
4	S/f anodized aluminium fixed partition in section 4"x1-3/4" with 4mm thick plain/frosted glass.	1.51	Sqm.	
5	S/f of anodized aluminum sliding panel window with aluminum section 4x1-3/4x2" section of aluminium frame and 5mm. thick frosted glass including all labour material t&p etc.	4.11	Sqm.	
6	P/f of Nova pan board in place of plain glass.	0.89	Sqm.	
7	Providing and fixing anodized aluminium grill with masquito wire gauge.	4.11	Sqm.	
8	Scraping old white or colour wash including disposal of refuse material as directed by Engineer-in-charge with a distanse as distance of 60 met.	55.00	Sqm.	
9	P/L of Cement based white putty for making good and smooth surface on old surface.	121.71	Sqm.	
10	Distempering with oil bound distemper two coat of approved brand on decorated wall surfaces togive an even shade including all materials, lobours T&P etc. complete .	81.81	Sqm.	
11	Application of two coats apex ultima paint on outer surface of wall including supply of all materials, labours and T&P etc.for proper completion of the work.	39.90	Sqm.	

Terms & condition

1. The quotation should be accepted by Registered Contractor of KGMU.
2. The rates should be quoted excluding G.S.T.
3. The work will completed within one week from the date of order.
4. The quotation should be reached by Registered post upto date mentioned in quotation.

Yours faithfully

Ram Velas Verma

(Ram Velas Verma)
Executive Engineer

Vel

No. *4385-96/2019-59*
/ of dt.

1. Registrar, K.G.M.U, Lucknow.
2. Finance Officer, K.G.M.U U.P, Lucknow.
3. Head of Department of Lari Cardiology Department K.G.M.U, Lucknow.
4. Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan, KGMU for Uploading the quotation Notice in KGMU.
5. Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow.
6. Junior Engineer , Works deptt. K.G.M.U. U.P, Lucknow.
7. Notice Board.

Ram Velas Verma

(Ram Velas Verma)
Executive Engineer

Vel