



# किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003 निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: -----

दिनांक: .....

15/01/2020

## QUOTATION NOTICE

To,

M/s.....

.....

.....

The sealed quotations are invited for Supply and Fixing Barbed wire outside boundary wall, M.S Gate (Generator area) and other misc.work at P.H.C Sarojini nagar from the registered contractor of KGMU. The detail of quotation notice can be seen at website [www.kgmcindia.edu](http://www.kgmcindia.edu) and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated

..... 23/01/20.....  
Details of the work as given below-

S.No.	Particulars	Quantity	Unit	Rate
1.	Earth work excavation in trenches for foundations in ordinary soil including lift upto 1.5 m. lead upto 50m and dressing of sides and rammings of bottom .	5.18	Cum.	
2.	P/L PCC 1:6:12 cement, fine sand & 40mm brick ballast.	1.14	Cum.	
3.	M-150 Class brick work 230mm thick in 1:4 cement coarse sand in foundation. including supply of all materials, labours and T&P etc. for proper completion of the work.	0.45	Cum.	
4.	M-150 class 230mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc. for proper completion of the work.	0.51	Cum.	
5.	M-150 class 120mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc. for proper completion of the work.	0.71	Cum.	
6.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	18.48	Sqm.	
7.	P/L cement concrete in 1:2:4 cement ,coarse sand 20mm stone grit.	1.61	Cum.	
8.	Fabrication of M.S Gate with M.S Angle, M.S Sheet and MS Flat. <i>angle iron</i>	396.18	Kg.	

*ed*



# किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

## निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.


दिनांक:.....

9.	Fencing with angle iron post placed at required distance embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be struted on both sides and provided with horizontal lines and two diagonals interwoven with horizontal wires, of barbed wire weighing 9.38 kg per 100m (minimum), between the two posts fitted and fixed with G.I staples, turn buckles etc. complete. (Cost of posts, struts, earthwork and concrete work to be paid for separately). with G.I barbed wire.	482.00	Rmt.	
10.	Applying one coat white cement on new surface.	18.48	Sqm.	
11.	Application of two coats apex Ultima paint on outer surface including supply of all materials, labours and T&P etc. for proper completion of the work.	18.48	Sqm.	
12.	Painting two coats with Superior synthetic enamel paint on new Surface including one coat primer.	24.28	Sqm.	
13.	Providing labour for cleaning of site and collecting malwa.	08	Nos.	
14.	Cartage for disposal of malwa up to 10km away from site.	23.20	Cum.	

### Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.


Yours faithfully

  
(Dinesh Kumar Raj)  
Executive Engineer

No. 0898-02/M10 of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. ~~Dr. Sandeep Bhattacharya, Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 15.11.2020 To 23.11.2020~~
3. Sri Anjani Kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri T.C Yadav, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.

  
(Dinesh Kumar Raj)  
Executive Engineer