किंग जार्ज चिकित्सा विश्वविद्यालय उ0प्र0, लखनऊ-226003

(विद्युत/यांत्रिक)विभाग

गाँधी स्मारक एवं सम्बद्ध चिकित्सालय,

पत्रांक .1094....नोटिस/ई0ई0(ई0/एम0)/26 दिनाँक 24/10/.2026

Quotation Notice

The sealed Quotations are invited for Medical Gas Pipe line Work in Critical care TVU ward at Trauma Center, KGMU Lucknow. The details of quotation can be seen at the Notice board of the office of undersigned. Interested parties may submit their quotations(For the purpose for estimated Cost of Work) to the office of undersigned by post or by hand duly marked on the envelope the number and date of this notice latest by dated....29/10/26.....

S.No.	Description	Unit	Qty	Rate	Amount Without GST
1.	Dismantling charges of Copper Pipes 12 mm(Including Plastic Saddles, Screws, Plastic Sleeves, Copper Fittings, Miscellaneous items etc)	Mtr	21		
2.	Dismantling charges of Copper Pipes 15 mm(Including Plastic Saddles, Screws, Plastic Sleeves, Copper Fittings, Miscellaneous items etc)	Mtr	80		
3.	Dismantling charges of Gas outlets(Including Plastic Saddles, Screws, Miscellaneous items etc)	Nos	68		
4.	Dismantling charges of Gas Alarm(Including Fasteners, Miscellaneous items etc)	Nos	01		
5.	Dismantling charges of Valve Box(Including Fasteners, Miscellaneous items etc)	Nos	01		
6.	Dismantling charges of 15mm Isolation Valve	Nos	8		
7.	Supply, fixing testing and commissioning of Medical Grade Copper Pipe used should be half drawn, tampered seamless phosphorous Deoxidized non-arsenic and degreased confirming to latest BS: EN: 13348, LLOYD Certified, including casing conduct etc. of suitable size & quality for underground and Overhead pipes and all Accessories like bends, tees, reducers etc. (Complete in all respect.)				
a.	12 MM (OD)x 0.9 MM(thickness)	Mtr	312		
b.	15 MM (OD)x 0.9 MM(thickness)	Mtr	198		
c.	22 MM (OD)x 0.9 MM(thickness)	Mtr	105		
8.	Supply, fixing testing and commissioning of Terminal Outlets gas specific for the services indicated (viz. O2, Air & Vacuum) and to accept only compatible quick connect Pin/Geometric Index type adapters as per ISO 7396 standard. Manufactured in compliance with CE and ISO 13485.				

किंग जार्ज चिकित्सा विश्वविद्यालय उ0प्र0, लखनऊ

(विद्युत/यांत्रिक)विभाग,

गॉधी स्मारक एवं सम्बद्ध चिकित्सालय,

पत्रांक .....नोटिस/ई0ई0(ई0/एम0)/26 दिनाँक.....2026

a.	BS Type Oxygen Outlet with matching probe/adaptor.	Nos	56		
b.	BS Type Medical Air Outlet with matching probe/adaptor.	Nos	56		
c.	BS Type Vacuum Outlet with matching probe/adaptor.	Nos	56		
9.	Supply, fixing, testing and commissioning of The Bed Head Panel (size 2.50 ft) shall be wall-mounted and fabricated using high-grade extruded aluminum profiles with a powder-coated finish, ensuring corrosion resistance and long-term durability.The panel shall be equipped with five (06) medical gas outlet points conforming strictly to BS Standard, color-coded as per HTM 02-01 / ISO 7396-1 guidelines.	Nos	28		
10.	Supply, fixing, testing and commissioning of FA Valve. The FineAdjustable Valve shall be of hospital-grade quality, designed precise regulation of gas flow in critical infrastructure systems. Itmust be manufactured from forged brass or stainless steel (SS304/SS 316) with PTFE/Teflon seals to ensure durability andcorrosion resistance. The valve shall operate within a pressurerating of not less than 10 bar. It must incorporate a fine-threadstem with micrometer-type adjustment for accurate flowcontrol, and be provided with BSP/NPT threaded endconnections conforming to IS/ANSI standards. The valve shall beleak-proof under rated pressure as per IS 778/ISO 5208.Compliance with IS 778, ISO 5208, NPPA guidelines	Nos	10		
11.	Supply, fixing, testing and commissioning of Gas lockable AVSU/CONTROL-CLOSING VALVE BOXES with integrated alarm system as required. Microprocessor based module. Digital LED display of "Normal", "High" & "Low". Digital pressure unit display options - psi/ bar or kg/cm2. Audio Mute option.				
A.	3 Gases AVSU.	Nos	01		
12.	Supply, fixing, testing and commissioning of Valve Box 3 Gas services	Nos	01		
13.	Supply, fixing, testing and commissioning of indigenous 12mm isolation valve.	Nos	168		
14.	Supply, fixing, testing and commissioning of indigenous 15mm isolation valve.	Nos	11		
15.	Supply, fixing, testing and commissioning of indigenous 22mm isolation valve.	Nos	02		
16.	Supply, fixing, testing and commissioning of Indigenous BPC Oxygen Flow Meter with Humidifier Bottle. (0-15L/Min)	Nos	28		
17.	Supply, fixing, testing and commissioning of indigenous Ward Vacuum unit with Vacuum Collection Jar size 1000ml as per BS: EN: IS 10079-3 and CE marked.	Nos	28		

किंग जार्ज चिकित्सा विश्वविद्यालय उ0प्र0, लखनऊ-226003

(विद्युत/यांत्रिक)विभाग,

गाँधी स्मारक एवं सम्बद्ध चिकित्सालय,

पत्रांक ..1094...नोटिस/ई0ई0(ई0/एम0)/26 दिनाँक 24/10/..2026

18.	Supply, Fixing, testing and Commissioning of Indigenous Low-Pressure Tube	Mtr	90		
19.	Supply, Fixing, testing and Commissioning of Accessories shall include one (01) wall-mounted stainless steelutility basket for Suction Unit / Suction Jar. The completeassembly shall comply with HTM 02-01, ISO 7396-1, and IEC 60601 standards.	Nos	28		
20.	Supply, Fixing, testing and Commissioning of Dual stage dual Gauge High Pressure Regulator	Nos	07		
21.	Supply, Fixing, testing and Commissioning of Emergency 4 Nos Cylinder Manifold- Oxygen(incl. NRV, Tailpipe & Middle frame with Chain for Cylinder.	Nos	07		
				Gross Total	

Term & conditions

1. All the work shall be completed within the given time period as per work order.
2. G.S.T. paid as per applicable.
3. Quantity can be increase of Decrease as per requirements.
4. Conditional quotaion are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

Executive Engineer(E/M)
King George's Medical University
Lucknow.

Section No.1094.....**Notice/E.E(E/M)/26 .of Date.**24-10-26.....

Copy for information and necessary action to :-

1. Notice Board.

Executive Engineer(E/M)
King George's Medical University