



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ-226003  
कार्यालय अधिशासी अभियंता (विद्युत/यंत्रिक)

पत्रांक.....1358/EE(EIM)

दिनांक 25.9.2023

**Urgent Quotation Notice**

**Sub: -Replacement of defective ceiling fitting & other misc. Electric work at Microbiology department, KGMU, Lucknow.**

Kindly submit your Quotation/Estimate for providing the following work in sealed envelope to the undersigned in the interest of patient care/institution within 3 days from the date of dispatch.

S.No.	Particulars	Qty.	Rate in each	Amount in Rs.
1	S F of metallic sheet enclosure 20 amp. As per PS No 1031	01 No.		
2	S F of LED fitting 18/20 watt complete in all respect.	02 Nos.		
3	F of 2'x2' 36-46 watt indoor recess mounting LED square fitting complete in all respect. As per PS No 1406	04 Nos.		
4	S F of wall fan 400mm.	01 No.		
5	S/F of submain 2x 4 sq.mm with multistrand single core copper as per PS No 216 Cwire.	30 Mtrs.		
6	S/F of 63 4 pole isolator	01 No.		
7	S/F of 6-32 amp MCB as per PS No. 1002	02 Nos.		
8	Supply and Burning of safe earthing electrode T 39 CU Copper Coted Length 3000 mm outer Pips 48 mm x 3.2 mm enner pipe 26.9 mm x 2.6 mm Terminal Dia 12 mm cotting 80-100 micron filled with Crystalline conductive mixture (ccm) having corrosive & conductive property with 50 Kgs activated Soil BPC Capable of Reducing the soil resestivity Good mixture of Retaining capacity alog with 30 Cm Square C.I. frame with hinged cover & Masonry housing from electrod terminal to Switch brod. The Cost of 25 mm x 3 mm Copper Strip will be extra. As per PS No 727 B	01 No.		
9	S/F of earth wire 8 SWG copper wire as per PS No 722	52 Mtrs.		
10	Dismantling charges of burnt of four pole isolator of DB & dismantling of incoming & outgoing connection & removing the carbon to restore the electricity	01 No.		
<b>Total</b>				

**Terms & Conditions:-**

1. G.S.T. : As Applicable.
2. All the works shall be completed within the given time period as per work order.
3. Quantity can be increase or decrease as per requirements.
4. All the works shall be carried out as per PWD specifications.
5. Firm should fill the A.R. Rate other than schedule Rate.
6. Contractor having experience in electrical department KGMU Lucknow can quote their rates.

Your Faithfully

Executive Engineer (Electrical)  
K.G.M.U.U.P., LUCKNOW

No.....of DT.....

**Copy for information and necessary action to:-**

1. Dr. Richa Khanna, Faculty In charge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from.....
2. Notice board.

Executive Engineer (Electrical)  
K.G.M.U.U.P., LUCKNOW