किंग जार्ज चिकित्सा विश्वविद्यालय उ0प्र0, लखनऊ–226003

निर्माण विभाग (यॉत्रिक खण्ड)

कोटेशन आमंत्रण हेतु सूचना

पत्र संख्या 40/DEE(Mech)/26
दिनाँक 23/10/26

सेवा में,

M/S:----------

कृपया अवगत कराना है कि के0जी0एम0यू0 के आम्रपाली योजना स्थित भवनों Staff Residence Type-I Block A, Staff Residence Type-I Blcok B, Resident Doctors Quarters Type-II Blcok A, Resident Doctors Quarters Type-II Blcok B, Resident Doctors Quarters Type-II Blcok C, Resident Doctors Quarters Type-III Blcok A, Resident Doctors Quarters Type-III Blcok B, Resident Doctors Quarters Type-III Blcok C, Faculty Residence Type-IV Block B का अग्निशमन विभाग द्वारा निरीक्षण/परीक्षण करने के उपरान्त अग्निसुरक्षा प्रमाण-पत्र करने के लिये फायर से सम्बन्धित कार्य कराने की आवश्यकता है जिनका विवरण निम्नवत् है:-

S.No	DESCRIPTION	QTY.	UNIT	RATE	AMOUNT
1	Providing, Laying, Testing & Commissioning of C- class heavy duty MS pipe on surface Confirming to IS 1239 (part-1) for pipes upto 150mm dia and IS:3589-1991 for pipes above 150mm. including cutting & welding with fitting like elbows, tees, hanger, flenges, taper, reducers, nuts, neoprene gasket & washer including cutting, welding etc.fixing the pipe ontheWall /Ceiling with suitable clamp and painted with red oxide and PO red enamel paint complete in all resspects.				
(A)	100 mm. Dia	190	M		
(B)	80mm. Dia	10	M		
(C)	25mm. Dia	30	M		
2	(A) Supplying, installation, testing and commissioning of electric driven terrace pump suitable for automatic operation and consisting of following, complete in all respects, as required: (Terrace Pump)				
(A)	**450 lpm at 35m Head**	8	Nos.		
3	Supplying, fixing, testing & commissionof **butterfly valve** of PN-16 slim seal standerd lever operated type as per designstanderd IS:1395 or BS:5155 with required flanges, nut bolts etc.complete in all respects.				
(A)	100 mm.dia	16	Each		
4	Providing, installation, testing and commission of **non-return valve** of following sizes PN-10 as per design standerd IS:5312 or BS:1868 with companion flanges, bolts, nuts, washers etc. complete in all respects.				
(A)	100 mm.dia	8	Each		
5	Supplying and fixing first-aid Hose Reel with MS construction spray painted in post officered, conforming to IS 884 complete with the following asrequired 20mm. nominal internal dia water hose thermoplastic(Textile reinforced) type-2 as per IS:12585 20 mm. nominal internal dia gun metal globe valve & nozzle. Drum and brackets for fixing the equipments on wall. Connections from riser with 25 mm dia stop gun metal valve & M.S. Pipe and socket.				
(A)	30m.	24	Set		
6	Supplying, Installation, testing & Commissioning of 25 mm. Air Release valve gunmental having rubber ball and with 25 mm. BSP threaded male inlet including necessary accessories and connections complete in all respect.	8	Set		
7	Supplying, Installation, testing & Commissioning of 25 mm. Ball valve PN-1 gunmental as per IS:778 including necessary Accessories and connections.	32	Set		
8	Providing & fixing of Weather proof standard fire hose cabinetboxmade out of 18 gauge MS sheet including two coats of postoffice redpaint over one coat of primer with 4 mm, thick glassdoor onfrontpainted"FIRE"in red luminious paint, The sizeofthe box should be750 mm X600 mm X250 mm size capableof accommodation a pairof hose with coupling and nozzel. Thebox should be floor mountedtype with railway coach lockarrangement and lever for opening thedoor after breaking the Glass complete.	24	Nos.		

किंग जार्ज चिकित्सा विश्वविद्यालय उ0प्र0, लखनऊ–226003

निर्माण विभाग (यॉत्रिक खण्ड)

कोटेशन आमंत्रण हेतु सूचना

पत्र संख्या .....

दिनाँक.....

9	Supplying and fixing 63mm. dia, 15m. long RRL hose pipe With 63 mm. dia male and female couplings duly bound with Gl wire, rivets etc. conforming toIS636(type-A) as required :				
(A)	Stainless Steel	24	Nos.		
10	Supplying & fixing 63mm. dia gun metal short branch pipe with 20mm. nominal internal diameter size nozzle conforming to IS 903 suitable for instantaneous connection to interconnect hose pipe coupling as required:				
(A)	Stainless Steel (Grade 304)	24	Nos.		
11	Supplying and fixing Single headed external yard hydrant valve with 1No. 63mm. dia instantaneous FM Gunmetal/Stainless Steel coupling and cast ironwheel, ISI marked, conforming to IS5290 (typeA) with blank Gunmetal/Stainless Steel cap and chain as required.				
(A)	Single headed Gunmetal	24	Nos.		
12	Supplying and fixing air vessel made of 250 mm dia, 8 mm. thick MS sheet, 1200mm. in height with air release valve on top and flanged connection to riser, drain arrangement with 25 mm. dia gun metal wheel valve with required accessories, pressure gauge and painting with synthetic enamel paint of approved shade as required.	8	No.		
13	Providing & fixing of pressure gauge in ranging from 0 to7 kg. per sqmm. ISI marked from approved manufacturers complete in all respects.	8	No.		
14	Providing/Fixing of Cubical type floor mounted Fire pump **Control panel** fabricated from 16G M.S. sheet duly powder coated finish of aproved shade and comprising of: a) One 63amp. TP+NL M.C.C.B. with rotary handle of beacking capacity 35 KA. b) One Voltmeter (0-500V) with selector switch. c) One set including lamps	8	No.		
15	Supply and laying of alluminium conductor PVC insulated armoured served sheathed cables 1100 volts grade at a depth of 750 mm. below ground level over a cushion of 75mm. thick sand all around and protected with burnt bricks on side and on top on surface the cable run shall be fied on M.S. clamps etc. of suitable size or as directed by the Engineer-in-charge, completein all respect. The armouring of the cable shall be properly connected with the earth conductor by clamps etc.				
(A)	10 sqmm. 4core	200	M.		
16	Providing and fixing pressure switch in M.S. pipe line including connection as required.	8	No.		
17	Providing and placing on terrace (at all floor levels) polyethylene water storage tank (5000Ltr.) ISI: 12701 marked indicating the BIS License No. with cover and suitable locking arrangement and making necessary holes for inlet, outlet and over flow pipes but without fitting and base support for tank.[Sintex, Electroplast, Star, Lotus or equivalent having valid ISI license].	8	Nos.		
18	Supply & fixing of CO2 type fire extinguisher, 4.5 kg. capacity (ISI Marked IS:2878 & TAC approved) comlete with initial charge and wall bracket, along with supply of all materials and labour for proper completion of work.	9	No.		
19	Supply & fixing of Modular fire extinguisher, ABC type 6.00 kg. capacity (ISI Marked IS:15683 & TAC approved) comlete with initial charge and wall bracket, along with supply of all materials and labour for proper completion of work.	27	No.		
	Fire Alarm System				
20.0	Supplying, installation, testing & commissioning of 4 Zone sector panel complete with visual indications for short circuit fault, open circuit fault, fire condition and all other standard facilities as per IS:2189 with mimic diagram for all area/zone covered, complete with all connections, interconnections as required.	8	Set		

किंग जार्ज चिकित्सा विश्वविद्यालय उ0प्र0, लखनऊ–226003
निर्माण विभाग (यॉत्रिक खण्ड)

कोटेशन आमंत्रण हेतु सूचना

पत्र संख्या .....
दिनाँक.....

21	Supplying, installation, testing & commissioning of manual call boxes of MS construction in surface/recess with stainless steel chain & hammer assembly complete with glass and push button etc. as required.	24	No.		
22	Supplying, installation, testing & commissioning fire alarm sounder in M.S. box (16 SWG) with hinged cover plate & suitable for operation with 24 Volt DC plate etc. complete as required.	24	No.		
23	Supplying & laying of 2x1.5 sqmm fire survival armoured cable, 600/1000V with annealed copper conductor having glass mica fire barrier tape covered by extruded layer of Cross Linkable Ethylene Propylene Rubber (EPR) insulation LSZH inner bedding, steel wire armouring & LSZH outer sheath	500	Mtr		
24.	Prepairing of Maps- Key plan, site plan, floor wise plan, front side elvation, floor wise fire fighting system plan, basement fire fighting plan as per NBC Guideline.	01	Job.		
				Total	
				GST@18%	
				Grand Total	

अतः किंग जार्ज चिकित्सा विश्वविद्यालय उ0प्र0, लखनऊ के पंजिकृत ठेकेदार/बाजर की फर्मो से निम्न प्रारूप पर दिनांक 23.10.2026 से 27.10.2026 की दोपहर 02.00 बजे तक अधोहस्ताक्षरी के कार्यालय में उपरोक्त फायर से सम्बन्धित कार्य कराने के लिये कोटेंशन आमंत्रित किये जाते है। दिनांक 27.10.2026 को दोपहर 02.30 बजे खोला जायेगा जिसमें कोटेंशन दाता स्वयं या उनके प्रतिनिधि प्रतिभाग कर सकते है। जिसमें उपरान्त तदनुसार अग्रेत्तर कार्यवाही की जायगी।

नोटः- भुगतान कार्य करने के उपरान्त ही किया जायेगा।

नियम एवं शर्तेः-

1. कोटेशन दाता साइड का निरीक्षण/परीक्षण करने के उपरान्त ही प्रतिभाग करें।
2. कोटेंशन दाता का कोटेंशन में किसी प्रकार का निगोशिएसन करनें का अधिकार नही होगा।
3. सशर्त कोटेंशन मान्य नही होगे, एक या समस्त कोटेंशन बिना कारण बताये निरस्त करनें का पूर्ण अधिकार अद्योहस्ताक्षरी को होगा।

अधिशासी अभियन्ता (वि0/यॉ0)
के0जी0एम0यू0,लखनऊ।

क्रमांक.....दिनांक.....

प्रतिलिपि निम्नलिखत को सूचानार्थ एवं आवश्यक कार्यवाही हेतु प्रेषितः-

1. इंचार्ज आई0टी0 सेल, के0जी0एम0यू0 लखनऊ को के0जी0एम0यू0 की वेब-साइड पर अपलोड करने के हेतु।

अधिशासी अभियन्ता (वि0/यॉ0)
के0जी0एम0यू0,लखनऊ।