



# किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003 निर्माण विभाग



फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: -----

4583/  
24/10

दिनांक: 24/09/19

## QUOTATION NOTICE

The sealed quotation are invited for supply and fixing of S.S railing and other misc. work on ramp at Physiology department from the registered contractor of KGMU. The detail of quotation notice can be seen at website [www.kgmcindia.edu](http://www.kgmcindia.edu) and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 21/10/19.


Details of the work as given below-

S.No.	Particulars	Quantity	Unit	Rate
1.	Dismantling cement concrete or granolithic floors, including stacking of dismantling material as per direction by the E/I.	7.50	Sqm	
2.	Earth work in excavation in trenches for foundations in ordinary soil including lift upto 1.5 m. lead upto 50m and dressing of sides and rammings of bottom.	0.78	Cum	
2.	P/L PCC 1:6:12 cement, fine sand & 40mm brick ballast.	0.60	Cum	
3.	P/L cement concrete in 1:2:4 cement, coarse sand 20mm stone grit.	0.60	Cum	
4.	M-150 Class brick work 230mm thick in 1:4 cement coarse sand in foundation. including supply of all materials, labours and T&P etc. for proper completion of the work.	0.79	Cum	
5.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&P etc. for proper completion of the work.	2.25	Sqm	
6.	Providing and laying white cement based putty of average thickness 1mm of approved band on new surface.	2.25	Sqm	
7.	Application of one coats Ultima apex paint on outer surface of wall including supply of all materials, labours and T&P etc. for proper completion of the work.	2.25	Sqm	
8.	P/L Pavit floor tiles 300x300mm 20mm thick cement mortar in 1:4 cement coarse sand including grouting of jointes with white cement and matching pigment.	7.50	Sqm	
9.	S/F of S.S railing 304 grade 16 gauge with s.s balustrade of s.s pipe and top rail 50mm dia including welding, grinding, polishing and height of railing 900mm	7.50	Rmt	
10.	S/F Master pillar 100mm dia of stainless steel.	2.00	Nos	

### Terms & Conditions-

1. G.S.T & Labour cess shall be applicable as per rules.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

  
(Dinesh Kumar Raj)  
Executive Engineer