

**WORKS DEPARTMENT, KING GEORGE' MEDICAL UNIVERSITY
U.P. , LUCKNOW**

No.....2235 / M/10

of date.....
17/03/2021

QUOTATION NOTICE

To,
M/s.....
.....
.....

The sealed quotations are invited for Misc. repairing Civil work for room No.01,02,06,37,202,205,305 and water supply fittings work of N.C.L.R.H and New L.R.H at K.G.M.U.U.P. Lucknow from the registered contractor of KGMU.The detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned.Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 24/03/2021.
Details of the work as given below-

S.No.	Particulars	Quantity	Unit	Rate
1.	Dismantling of old door / windows/ventilators chaukhats with hold fast & including stacking of dismantled material.directed by the engineer incharge.	1.75	Sqm	
2.	P/L cement concrete in 1:2:4 cement, coarse sand 20mm stone grit.	0.02	Cum	
3.	Fabrication of M.S angle with M.S door and welding complete.	12.79	kg	
4.	P/F 40x5mm flat iron hold fast 40cm long including fittings bolts, nuts and woden plugs	04	Nos	
5.	Scraping old white or colour wash etc.including disposal of refuse material as directed by Engineer-in-charge.	150.91	Sqm	
6.	Providing and laying cement based white putty of average thickness 0.60mm of approved band and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	150.91	Sqm	
7.	Distempering with oil bound distemper two coat of approved brand old Surface to give an even shade including all material , labour T&P etc. complete.	738.30	Sqm	
8.	Painting two coat with Supirior synthetic enamel paint on old Surface including supply of labour material t&p etc. complete.	162.12	Sqm	
9.	Painting two coat with Supirior synthetic enamel paint on new Surface & one coat primer including supply of labour material t&p etc. complete.	5.02	Sqm	
10.	Providing and fixing flush door shutters 30mm thick including ISI Marked stainless steel but hinges with necessary screw.	2.10	Sqm	
11.	P/F PVC ball cock of appd. Quality colour and make complete with epoxy coated aluminium rod with LP/HPHD plastic ball.	02	Nos	
12.	P/f I.S.I. Marked Aluminum sliding tower bolt 16mm dia 250mm long with nuts &bolts	01	No	
13.	P/f Stainless steel I.S.I marked tower bolt with 10mm dia &screw 100mm long.	01	No	
14.	P/F C.P Long body bib cock 15mm dia. make of Cera, hindware.jaguar.	04	Nos	
15.	P/F S.S curtain rod 20mm dia	10.30	Rmt	
16.	P/F G.I pipe 32mm dai complete with G.I fittings.	1.50	Rmt	
17.	P/F G.I Union in G.I pipe line 32mm dai.	02	Nos	
18.	P/F door closer for Appd quality godrej or equivalent.	02	Nos	

1/2" of PVC waste pipe for wash basin/sink.	01	Nos	
1/2" of brass waste jaali for wash basin.	01	Nos	
Providing Carpenter with helper for repairing of old door/window.	02	Nos	
umber with helper for repair work for sanitary fittings.	01	Nos	

Conditions.


1. Material & Labour Cess shall be paid or deducted as per rules applicable.

2. Work will be completed within given time.

3. Quantity can be increase or decrease as per requirements.

4. Additional quotations are liable to be rejected.

Yours faithfully



(Ram Velas verma)

Executive Engineer

-41/M/10

...../ of DT.

Copy for information and necessary action to:-

1. Director, King George's Medical University U.P, Lucknow.

2. Deputy Commissioner, King George's Medical University U.P, Lucknow.

3. Chief Medical Superintendent, King George's Medical University U.P, Lucknow.

4. Richa khanna, Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading quotation Notice in KGMU, Website.

5. Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow

6. Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow

7. P.W. Board.



(Ram Velas verma)

Executive Engineer

