



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu

पत्रांक: -----

UGA/M/10

दिनांक: 10/06/2024

QUOTATION NOTICE

To,

M/s.....

.....

The sealed quotations are invited for Providing brickwork near front porch including repairing & painting work of OPD room in basement of shatabdi phase-II KGMU. The details of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned. Registered contractors of kgmu may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 18/06/2024

Details of work as given below:-

S.No.	Particulars	Quantity	Unit	Rate
1.	Scraping old white or colour wash etc.including disposal of refuse material as directed by Engineer-in-charge.	26.03	Sqm.	
2.	M-150 Class brick work in 1:4 cement coarse sand in foundation including supply of all materials, labours and T&P etc.for proper completion of the work.	0.91	Cum.	
3.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	8.71	Sqm.	
4.	Providing and laying cement based white putty of average thickness 0.60mm of approved brand and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	26.03	Sqm.	
5.	Providing and laying white cement based putty of average thickness 1mm of approved brand on new plastered surface to prepare the surface even and smooth complete.	8.71	Sqm.	
6.	P/L 18mm thick granite in required design and pattern with 1:4 cement coarse sand including all labour material etc. complete.	6.94	Sqm.	
7.	P/L cement concrete in 1:2:4 cement ,coarse sand 20mm stone grit.	0.89	Cum.	
8.	Distempering with oil bound distemper one coat of approved brand on old Surface to give an even shade including all material , labour T&P etc. complete.	44.32	Sqm.	
9.	Providing and fixing inter locking metal false ceiling grid of hot dipped galvanized steel sections consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm complete.	5.40	Sqm.	
10.	Providing and fixing brass curtain rods 25mm dia. of wall thickness 1.25 mm with two brass brackets fixed with brass screws and wooden plugs etc. wherever necessary complete.	3.25	Rmt.	
11.	Providing labour for cleaning of site and collecting malwa.	04	Nos.	

Terms & Conditions

1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.

18/06/2024



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 ई-मेल : eng.civil@kgmcindia.edu

पत्रांक: -----

दिनांक:.....

4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

Suresh Kumar

(Suresh Kumar)
Executive Engineer

No. *462 MM* / of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date *12/06/24* To *18/06/24*
3. Sri T.C. Yadav, Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow
4. Sri Poshit roy, Junior Engineer, Works deptt. K.G.M.U. U.P. Lucknow
5. Notice Board.

Suresh Kumar

(Suresh Kumar)
Executive Engineer

P. Roy
JE