WORKS DEPARTMENT, KING GEORGE'S MEDICAL UNIVERSITY U.P., LUCKNOW

No....5.8.89/M-10

Quotation Notice

of dt 27.1.1.19

Sub:- Misc Civil Painting (Ramp), Tile (water cooler) & other work, Deptt. of D.P.M.R. (R.A.L.C.),

K.G.M.U., U.P., Lucknow

28/11/19

Dear sir,

Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3:30 P.m on dated [1.1.1.1.1]

Sl.No	Particular	Quantity	Unit	Rates
1	Class-150 Brick work 230mm thick wall in 1:4 cement and	0.26		
	coarse sand in superstructure.		1000	
2	P/L Kajaria or equivalent wall tiles 300x600mm. with water	3.90	Sqm	14
	absorption less than 0.08% and conforming to IS:15622 of			
	approved make in all colours and sheds, lied on 20mm. thick			
	cement mortar in 1:4 cement and coarse send including grouting			
	of joints with white cement matching pigment.			
3	P/L of appd.quality Pavit floor tiles size 300x300mm. over	2.90	Sqm	
	20mm. thick base of 1:3 cement coarse sand in complete.			1.0
4	Scraping of colour white wash old surface.	132.00	Sqm	
5	P/L of Birla white putty for making good smooth surface.	132.00	Sqm	
6	Oil bound distemper in two coat.	674.74	Sqm	
7	Enamel painting in two coat	176.17	Sqm.	
8	P.V.C Pipe 100mm dia	3.00	Rmt	

Terms & Condition

- 1. The quotation should be accepted by Registered Contractor of KGMU.
- 2. The rates should be quoted excluding G.S.T. & Labuor Cess.
- 3. The work will completed within given time in the work order.
- 4. The quotation should be reached by Registered post upto date mentioned in quotation.

Yours Faithfully

(Ram Velas Verma) Executive Engineer.

No. 5890 -95/1

Date.....

Copy for Information and necessary action to:

- 1. Registrar, K.G.M.U, U.P. Lucknow
- 2. Finance Officer, K.G.M.U, U.P. Lucknow
- 3. Head of D.P.M.R. (R.A.L.C.)., K.G.M.U, U.P. Lucknow
- Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan, KGMU for uploading the quotation Notice in KGMU.
- 5. Assistant Engineer, Works deptt. K.G.M.U, U.P. Lucknow
- 6. Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow
- 7. Notice Board.

(Ram Velas Verma) Executive Engineer

(Civil Section) King George's Medical University Uttar Pradesh,

Lucknow.

Name of Work:- Misc Civil Painting (Ramp), Tile (water cooler) & other work, Deptt. of D.P.M.R. (R.A.L.C.), K.G.M.U., U.P., Lucknow

ABSTRACT OF ESTIMATED COST

O.N.	Quantity	Unit	Description	Rate	Per	Amount Rs.	Remarks
S.N. 1.	0.26	Cum	Class-150 Brick work 230mm thick wall in 1:4 cement and coarse sand in superstructure.	5500.00	Cum	1430.00	Chap No-6 S.N. 305(b)+309
2.	3.90	Sqm	P/L Kajaria or equivalent wall tiles 300x600mm. with water absorption less than 0.08% and conforming to IS:15622 of approved make in all colours and sheds,lied on 20mm. thick cement mortar in 1:4 cement and coarse send including grouting of joints with white cement matching pigment.	1136.00	Sqm	4430.40	A.R.
3.	2.90	Sqm	P/L of appd.quality Pavit floor tiles size 300x300mm. over 20mm. thick base of 1:3 cement coarse sand in complete.	1020.00	Sqm	2958.00	A.R.
4.	132.00	Sqm	Scraping of colour white wash old surface.	12.00	Sqm	1584.00	Chap No-17 S.N.708
5.	132.00	Sqm	P/L of Birla white putty for making good smooth surface.	53.00	Sqm	6996.00	A.R
6.	674.74	Sqm	Oil bound distemper in two coat.	55.00	Sqm	37110.70	ChapNo15S. N.650,651
7.	176.17	Sqm.	Enamel painting in two coat	60.00	Sqm.	10570.20	Chap No- 15S.N.645,6 46
8.	3.00	Rmt	P.V.C Pipe 100mm dia	260.00	Rmt	780.00	M.R.
0.					Total	65859.30	
				GST 12%		7903.11 73762.41	
				Total Labour Cess 1%		737.62	
				Total		74500.03	
				Say		74500.00	-

Dated-----20

Asstt. Engineer
K.G.Medical University U. P.
Lucknow.

Junior Engineer K.G.Medical University U. P. Lucknow.

Executive Enigneer
K.G.Medical University U. P.
Lucknow.