

(Civil Section)  
King George's Medical University Uttar Pradesh,  
Lucknow.

No..... 1983/Mo

(580) 21/03/2021

of date 01/03/2021

QUOTATION NOTICE

To,  
M/s.....

The sealed quotation are invited for Misc. Civil work Slab False Ceiling, Aluminum & other work (Blood storage Center) New Building (Road side), Q.M.H. at K.G.M.U. U.P., Lucknow. from the registered contractor of K.G.M.U. The Detail of quotation can be seen at website [www.kgmcindia.edu](http://www.kgmcindia.edu) and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 01/03/2021

Details of the work as given below-

S.N.	Particular	Quantity	Unit	Rates
1.	R.C.C. Slab in 1:2:4 cement C-Sand stone aggregate.	0.16	Cum	
2.	P/L of 20mm approved quality of Red Lakha granite slab/stone in rise of steps skirting dodo walls and pillars, laid of 10mm thick base jointing with cement slurry including colouring all labour material T&P etc. upto the proper competition of the work as per direction of Engineer-in-charge.	2.10	Sqm	
3.	Mild Steel work 10/12mm dia as for reinforcement.	75.60	Kg.	
4.	P/F metal False Ceiling of appd. Quality with G.I. Section including all labour material all Complete as per direction of Engineer-in-charge.	13.90	Sqm	
5.	P/F Appd. Quality steel sink without drainage board size 1040x510x200mm with bracket waste jali waste pipe complete.	1.00	No.	
6.	P/F Anodized aluminum work for doors, windows and ventilators with extruded built up standard tabular section/ appropriate Z section and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia. and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required with rubber/neoprene gasket etc.	70.10	Kg.	
7.	P/F 4mm thick ACP sheet in aluminum work for doors, windows, ventilators shutters and partitions etc. with EPDM rubber /neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge.	10.40	Sqm.	
8.	Providing and fixing G.I. Pipe 15mm dia with fitting 'B' class.	10.15	Rmt	
9.	Oil bound distemper in two coat.	42.30	Sqm	

Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotation are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours Faithfully

*Verma*

(Ram Velas Verma)  
Executive Engineer

No. 1984-89/Mo Date 01/03/2021

Copy for Information and necessary action to:

1. Registrar, K.G.M.U, U.P. Lucknow
2. Finance Officer, K.G.M.U, U.P. Lucknow
3. H.O.D., Q.M.H., K.G.M.U, U.P. Lucknow
4. Dr. Richa khanna , Faculty Incharge, Website Administration Data Center, PHI Bhawan, KG MU for uploading the quotation Notice in KG MU, Website.
5. Assistant Engineer, Works deptt. K.G.M.U, U.P. Lucknow
6. Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow
7. Notice Board.

(Ram Velas Verma)  
Executive Engineer