

No. 1989/M/10

of date 01/03/2021

**QUOTATION NOTICE**

To, M/s.....

The sealed quotation are invited for **Misc. Civil work Repair of P.V.C. Pipe Outer Duct, COVID-19, R.A.L.C. at K.G.M.U. U.P., Lucknow.** from the registered contractor of K.G.M.U. The Detail of quotation can be seen at website [www.kgmcindia.edu](http://www.kgmcindia.edu) and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated.....

Details of the work as given below-

S.N.	Particular	Quantity	Unit	Rates
1.	Earth work in Surface excavation not exceeding 30cm in depth but exceeding 1.5m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50m and lift upto 1.5m, as directed by Engineer-in-charge. 2.1.1 all kinds of soil. 0 to 0.30m	5.76	Cum	
2.	Dismantling Brick work or stone work in lime are cement mortar and including stacking of material as directed by the Engineer-in-charge complete etc.	1.44	Cum	
3.	P/L P.C.C. 1:5:10 cement, fine sand and 40mm brick ballast in foundation.	0.76	Cum	
4.	40mm thick flooring 1:2:4 cement C-sand stone Aggregate of with floating coat of neat cement.	9.60	Sqm	
5.	M-150 class 120mm thick brick work in 1:3 cement & coarse sand in super structure including supply of all materials, labours and T&P etc for proper completion of the work.	25.10	Sqm	
6.	12mm thick plaster 1:4 cement C-Sand in wall.	25.10	Sqm	
7.	C.C. work in 1:2:4 cement C-Sand stone aggregate.	1.89	Cum	
8.	S/f of P.V.C. Pipe 150mm dia with fitting.	19.20	Rmt	
9.	4mm thick Glass with Putty complete.	22.10	Sqm	
10.	P/L of Birla white putty for making good smooth surface.	25.10	Sqm	
11.	Application of two coats Apex. Ultima paint of Approved Brand on old Surface Given an even Shade including supply of all material, labour T&P as required for proper completion of work.	45.10	Sqm	
12.	Providing Plumber with helper repairing for old sanitation work.	2.00	No	
13.	Cartage of malwa from back side of main hospital building up to 3km away from the K.G.M.U. campus.	4.15	Cum	

**Terms & Conditions.**

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotation are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours Faithfully

*Ram Velas Verma*

(Ram Velas Verma)  
Executive Engineer

No. 1970-75/M/10

Date.....

Copy for Information and necessary action to:

1. Registrar, K.G.M.U, U.P. Lucknow
2. Finance Officer, K.G.M.U, U.P. Lucknow
3. H.O.D., D.P.M.R(R.A.L.C), K.G.M.U, U.P. Lucknow
4. Dr. Richa khanna, Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU, Website.
5. Assistant Engineer, Works deptt. K.G.M.U, U.P. Lucknow
6. Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow
7. Notice Board.

*Ram Velas Verma*

(Ram Velas Verma)  
Executive Engineer