

**WORKS DEPARTMENT, KING GEORGE'S MEDICAL UNIVERSITY
U.P, LUCKNOW**

of dt. 01/11/19

No. 5410/M-10

Quotation Notice

Sub:- Misc Civil Brick, Red Lakha, Aluminium & other work, Medicine O.P.D., 1st Floor, Deptt. of Old O.P.D., K.G.M.U., U.P., Lucknow

Dear sir,
Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3:30 P.m on dated. 01/11/19

Sl.No	Particular	Quantity	Unit	Rates
1	Class-150 Brick work 1:4 cement C-Sand in wall Superstructure below 12c.m. thick.	0.71	Cum	
2	R.C.C. Slab in 1:2:4 cement C-Sand stone aggregate.	0.25	Cum	
3	Mild Steel work 10/12mm dia as for reinforcement.	18.30	Kg	
4	Pvoding and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18mm thick stone slab over 20mm (average) thick base of cement mortar 1:4 (1 cement:4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-charge.(Polished Granite stone slab jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.)	3.09	Sqm	
5	S/F anodized aluminium door 2mm thick fully glazed made aluminium door tube size 83.50x44.65mm as vertical member 114.00x44.65mm with 5mm thick glass.	1.57	Sqm	
6	S/F of Aluminium fixed partition 4"x1 3/4"x2mm. aluminium section with Aluminium Grill including all Labour material T & P. etc.	9.21	Sqm	
7	P/L Kajaria or equivalent wall tiles 300x600mm. with water absorption less than 0.08% and conforming to IS:15622 of approved make in all colours and sheds, lied on 20mm. thick cement mortar in 1:4 cement and coarse send including grouting of joints with white cement matching pigment.	4.97	Sqm	
8	P/L of 20mm. approved quality of Red Lakha granite slab/stone in rise of steps skirting dodo walls and pliiars, laid of 10mm. thick base jointed with cement slurry including colouring all labour material T & P etc. upto the proper competition of the work as per dirction of Engineer-in-charge.	4.12	Sqm	

Terms & Condition

1. The quotation should be accepted by Registered Contractor of KGMU.
2. The rates should be quoted excluding G.S.T. & Labuor Cess.
3. The work will completed within given time in the work order.
4. The quotation should be reached by Registered post upto date mentioned in quotation

Yours Faithfully

Ram Velas Verma
(Ram Velas Verma)
Executive Engineer

No. 5411-16/M-10

Date.....

Copy for Information and necessary action to:

1. Registrar, K.G.M.U, U.P. Lucknow
2. Finance Officer, K.G.M.U, U.P. Lucknow
3. Incharge, OLD O.P.D., K.G.M.U, U.P. Lucknow
4. Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan, KGMU for uploading the quotation Notice in KGMU.
5. Assistant Engineer, Works deptt. K.G.M.U, U.P. Lucknow
6. Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow
7. Notice Board.

Ram Velas Verma
(Ram Velas Verma)
Executive Engineer