

## निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&amp;225753 वेबसाइट : www.kgmcindia.edu.

3367/M10

दिनांक:.....

28/05/2021

QUOTATION NOTICE

To, M/s.....

.....

The sealed quotations are invited for P/F PVC door in toilet and other misc. work in skill lab at General Surgery department from the registered contractor of KGMU. The detail of quotation notice can be seen at website [www.kgmcindia.edu](http://www.kgmcindia.edu) and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 28/05/2021.....Details of the work as given below-

Sl.No.	Particulars	Qty.	Unit	Rate
1	Dismantling existing old plaster including disposal of refuse as directed by engineer incharge	4.35	Sqm	
2	Dismantling cement concrete or granolithic floors, including stacking of dismantling material as per direction by the E/I.	6.28	Sqm	
3	P/L PCC 1:6:12 cement, fine sand & 40mm brick ballast.	0.50	Cum	
4	M-150 class 120mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc. for proper completion of the work.	5.88	Sqm	
5	P/L Vitrified wall tiles 300x600mm with water absorption less than 0.08% and conforming to IS: 15622 of approved make in all colours and sheds, laid on 12mm thick cement mortar in 1:3 cement coarse sand including grouting of jointes with white cement and matching pigment.	4.35	Sqm	
6	P/L vitrified floor tiles in 600x600mm (thickness to be specified by the manufacture) with water absorption less than 0.08% and conforming to IS: 15622 of approved make in all colours and sheds, laid on 20mm thick cement mortar in 1:4 cement coarse sand including grouting of jointes with white cement and matching pigment etc. complete.	6.28	Sqm	
7	S/f of Descon make or equivalent Solid PVC door frames of 65mm x 46mm & shutter 25mm (Solid thick with ribs) Grey/Dark Grey/Black thick mode of Foam PVC sheet including Aluminum hardware, sliding bolt, Handles & hinges.	6.62	Sqm	
8	Providing and fixing 4 mm thick ACP sheet.	5.87	Sqm	
9	P/F anodised aluminum work for partitions with extruded built up standerd tubular section Z section and other section of approved make conforming to IS: 733 and is: 1285 fixing with dash fasteners of required dia size including necessary fittings up the gaps at junctions I.E at top, bottom, and sides with required EPDM rubber/ neoprene gasket etc. complete.	27.00	Kg	



# किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003 निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

दिनांक:.....

## Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

(Dinesh Kumar Raj)  
Executive Engineer

  
JE  
A E

3368-72/M/10  
No. .... of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 20/05/21 To 26/05/21
3. Sri Suresh Kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri T.C Yadav, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.

(Dinesh Kumar Raj)  
Executive Engineer

  
JE  
A E