



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003  
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 Email : eng.civil@kgmcindia.edu

पत्रांक: -----

422/MU

दिनांक:.....

05/06/2024

QUOTATION NOTICE

To,

M/s.....

.....

.....

The sealed quotations are invited providing boundary wall between new mortuary and laundry at dhobi ghaat from the registered contractor of KGMU. The detail of quotation notice can be seen at website [www.kgmu.org](http://www.kgmu.org) and on the Notice board of the office of undersigned Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 12/06/2024.....

Details of the work as given below-

Sl.No.	Particulars	Qty.	Unit	Rate
1	Earthwork in excavation in trenches for foundations in ordinary soil including lift upto 1.5m lead upto 50m and dressing of sides and rammings of bottom.	2.75	Cum.	
2	P/L PCC 1:5:8 cement, fine sand & 40mm stone ballast.	0.46	Cum.	
3	M-150 class 230mm thick brick work in 1:4 cement & coarse sand in foundation including supply of all materials, labours and T&P etc. for proper completion of the work.	1.50	Cum.	
4	M-150 class 230mm thick brick work in 1:4 cement & coarse sand in super structure including supply of all materials, labours and T&P etc. for proper completion of the work.	2.72	Cum.	
5	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	31.23	Sqm.	
6	P/L cement concrete in 1:2:4 cement, coarse sand 20mm stone grit.	1.33	Cum.	
7	Applying one coat of water thinnable cement primer of approved brand on new plastered wall surface.	31.23	Sqm.	

*Handwritten signature*  
J.E



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003  
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 Email : eng.civil@kgmcindia.edu

पत्रांक: -----


दिनांक: .....


8	Providing and laying white cement based putty of average thickness 1mm of approved brand on new plastered surface to prepare the surface even and smooth complete.	31.23	Sqm.	
9	Application of two coats apex Ultima paint on outer surface including supply of all materials, labours and T&P etc. for proper completion of the work.	31.23	Sqm.	
10	Mild steel work for reinforcement in plain cement concrete including binding, bending and cutting complete.	23.42	Kg.	
11	P/L R.C.C plinth beam in 1:1.5:3 cement, coarse sand and stone aggregate.	0.18	Cum.	
12	Providing and fixing 1mm thick M.S sheet door with frame of 40x40x6mm angle iron and 3mm M.S gusset plates at the junctions and corners, all necessary fittings complete including applying a priming coat of approved steel primer.	1.85	Sqm.	
13	Painting two coat with superior synthetic enamel paint on new surface and one coat primer including supply of labours, materials T&P etc complete.	3.70	Sqm.	
14	Providing labour for cleaning of site and collecting malwa.	06	Nos.	
15	Cartage for disposal of malwa up to 10km away from site.	8.14	Cum.	

Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

  
(Suresh Kumar)  
Executive Engineer

  
(Dinesh Kumar Raj)  
Superintending Engineer

  
J.E





किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003  
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 Email : eng.civil@kgmcindia.edu

पत्रांक: -----

दिनांक:.....

No...../ of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date *03/06/2024* .....To *12/06/2024*
3. Sri T.C Yadav, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri Abhishek Sharma, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.

Yours faithfully

*Suresh Kumar*  
(Suresh Kumar)  
Executive Engineer

*Dinesh Kumar Raj*  
(Dinesh Kumar Raj)  
Superintending Engineer

*A.S.*  
J.E