



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: 4508/M-10

दिनांक: 21/09/19

To,

M/s.....

The sealed quotations are invited for Providing and Laying Rubber moulding interlocking tiles for A.C plant of V.C office from the registered contractor of KGMU. The detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 28/09/19.....


Details of the work as given below-


S.No.	Particulars	Quantity	Unit	Rate
1.	Earth works in excavation in trenches for foundations in ordinary soil including lift upto 1.5 m. lead upto 50m and dressing of sides and rammings of bottom.	1.18	Cum.	
2.	P/L PCC 1:6:12 cement, fine sand & 40mm brick ballast.	3.11	Cum.	
3.	M-150 Class brick work 230mm thick in 1:4 cement coarse sand in foundation. Including supply of all materials, labours and T&P etc. for proper completion of the work.	0.90	Cum.	
4.	12 mm cement plaster finished with a floating coat of neat cement of mix 1:4 (1 cement: 4 fine sand).	9.03	Sqm.	
5.	P/L of appd. Quality 80mm thick unipaver (Zig-Zag) rubber molding interlocking tiles not less than 30MPa including leveling and dressing of surface to required level and slope, filling joints local sand and also including the cost of all material, labour T&p complete.	51.28	Sqm.	

Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully


(Dinesh Kumar Raj)
Executive Engineer


Dinesh Kumar