



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmciindia.edu.

पत्रांक

1123/MV

QUOTATION NOTICE

दिनांक

28/12/2022

To,

M/s.....

The sealed quotations are invited for making M.S frame for protection of A.C outdoor at I.C.T.C building and fencing with M.S swiss welded mesh at pathology building for microbiology department from the registered contractor of KGMU. The detail of quotation notice can be seen at website www.kgmciindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 25/12/2022.

Details of the work as given below-

S.No.	Particulars	Quantity	Unit	Rate
1.	Fabrication of M.S frame and structure with M.S angle, square bar for A.C outdoor.	636.52	Sqm.	
2.	P/F of swiss welded mesh 1"x1" 10 gauze with 20x5mm flat iron beading including all material labour T&p complete.	14.40	Sqm.	
3.	P/L Cement concrete 1:2:4 cement, coarse sand & 20mm stone grit and curing complete including of form work.	0.17	Cum.	
4.	Painting 2 coats with superior synthetic enamel paint on new surface with one coat primer upto 10 cm width or grith.	57.16	Sqm.	
5.	P/F M.S Hinges 125mm long ISI marked.	24	Nos.	
6.	Providing welding machine with welder for repairing of old M.S Structure.	01	No.	
7.	P/F double scaffolding system (cup lock type) on the exterior side of building/structure, upto 25 metre height, above ground level, including additional rows of scaffolding in stepped manner as per requirement of site, made with 40mm dia M.S Tube placed 1.5 metre centre to centre, horizontal and vertical tubes joint with cup and lock system with M.S Tubes, M.S Tube chalis, M.S clamps and staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for execution of work of cleaning and/or pointing and/or applying chemical and removing it thereafter. The scaffolding system shall be stiffened with bracings, runners, connecting with the building etc, wherever required, if feasible for inspection of work at required locations with essential safety features for the workmen etc, complete as per directions and approval of Engineer-in-charge.	7.50	Sqm.	

Rel
E

28/12/2022