



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org

पत्रांक: 498/ MME

दिनांक: 12/06/2021

QUOTATION NOTICE

To,

M/s.....

The sealed quotations are invited for repairing of old aluminum doors and water supply sanitary fittings and other misc. work of geriatric department and Queen Mary hospital kgmu. the detail of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 19/06/2021

Details of the work as given below-

Sl.No.	Particulars	Qty.	Unit	Rate
1.	Dismantling existing old plaster including disposal of refuse as directed by engineer incharge.	4.01	Sqm	
2.	Dismantling of GI Pipe 15mm dia to 50mm.	13.00	Rmt	
3.	Dismantling cement concrete or granolithic floors, including stacking of dismantling material as per direction by the E/I.	2.16	Sqm	
4.	Providing and fixing CPVC pipes 20mm dia including all CPVC plain & brass threaded fittings including fixing the pipe with clamps at 1.00 m spacing this includes jointings of pipes & fittings	13.00	Rmt	
5.	P/L wall tiles in size 300x200mm approved make in all colours and sheds, laid on 12mm thick cement mortar in 1:3 cement coarse sand including grouting of joints with white cement and matching pigment.	2.34	Sqm	
6.	P/L floor tiles in size 600x600mm with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and sheds laid on 20mm thick cement mortar in 1:4 including grouting of joints with white cement and matching pigment etc. complete.	2.16	Sqm	
7.	P/L pavit floor tiles in size 300x300x9mm with water absorption less then 0.05% and conforming to IS: 15622 of approved make in all colours and sheds , laid on 20mm thick base of 1:4 cement coarse sand in all complete	2.88	Sqm	
8.	P/L 12mm thick cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&P etc. for proper completion of work	0.45	Sqm	
9.	P/F PTMT bib cock 15mm dia make of appd quality	01	No.	
10.	S/f PTMT Angle valve 15mm of appd. Quality complete.	02	Nos	
11.	P/F C.P brass stops cock 15mm dia make of appd. Quality.	02	Nos.	
12.	P/F pvc pipe 100mm dia make of ISI appd quality.	7.16	Rmt	
13.	P/F PVC bend 100mm dia.	01	No.	
14.	S/F M.S clamp for C.I pipe 100mm dia.	02	Nos	
15.	Mild steel work for reinforcement in plain cement concrete including binding,bending and cutting complete	6.30	Kg	
16.	Fabrication of M.S structures with angles for fram including materials and labour complete	11.34	kg	
17.	P/L RCC work in cover in 1:1.5:3 cement, coarse sand and stone aggregate.	0.03	Cum	



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003

निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 वेबसाइट : www.kgmu.org

पत्रांक: -----

दिनांक:

18	Repairing of old aluminum doors with 8mm dia fully threaded tie rod with nut and washer including placing on proper position in aluminum door frame	44.49	Sqm	
19	P/F S.S hinges 100mm long with stainless steel screw etc.	40.00	Nos	
20	Providing & fixing 5mm thick glass panes with glazing doors, windows, ventilators, shutter and partition etc. with EPDM rubber/ neopren gasket etc. complete as per direction in charge	1.78	Sqm	
21	P/F 4mm thick glass panes with putty and glazing clips in steel doors, window, clerestory window all complete.	8.47	Sqm	
22	P/F aluminum sliding door bolt with 16mm dia and 250mm long.	02	Nos	
23	P/F aluminum handles with screw 125mm long.	12	Nos	
24	Providing and fixing door stopper 100mm long	12	Nos	
25	S/F of appd quality door closer ISI marked.	05	Nos	
26	Repairing of old chaanel gate.	01	No	
27	P/F inter locking metal false ceiling grid of hot dipped galvanized steel section consisting of main tee runner with sutableing spaced joint "T" gates required length and of size 24x38mm made from 0.30mmthick sheet, spaced and 1200mm center to center and cross tee of size 24x25mm made of 0.30mm thick sheet, 1200mm long spaced between main "T" at 600mm center to center from to grid.	15.02	Sqm	
28	P/F C.P brass angle valve for wash basin of appd quality.	01	No.	
29	Providing Sweeper for cleaning of mainhole and sewer line by sweeper with tools including disposal of garbage as per direction of site incharge	05	Nos	
30	Providing Plumber with helper for repairing of old fitting	02	Nos	
31	Providing labour for cleaning of site and collecting malwa	03	Nos	

Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

(Anupam mishra)
Executive Engineer

No. 496/MS10 of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 12/06/24 To 19/06/2024
3. SriYashwant singh, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri Sumit kanaujia, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.

(Anupam mishra)
Executive Engineer