किंग जार्ज चिकित्सा विश्वविद्यालय उ0प्र0, लखनऊ– 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 बेवसाइट : www.kgmcindia.edu.

पत्रांक: 5802/M-10/2022 दिनांक: 09/09/22

QUOTATION NOTICE

To,

M/s.....
.....
.....

The sealed quotations are invited for Miscellaneous Repair and Painting of flat No.802 at teachers flat in T.G Campus. The detail of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned.Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 16/09/2022.....Details of the work as given below-

Sl.No.	Particulars	Qty.	Unit	Rate
1	Dismantling existing old plaster including disposal of refuse as directed by engineer incharge.	5.02	Sqm	
2	Dismantling of old door/ windows chaukhats with hold fast & including stacking of dismantled material directed by the engineer incharge.	3.49	Sqm	
3	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	2.32	Sqm	
4	P/L wall tiles 200x300mm with water absorption less then 0.08% and conferming to IS: 15622 of approved make in all colours and sheds , laid on 12mm thick cement mortar in 1:3 cement coarse sand including grouting of jointes with white cement and matching pigment	2.26	Sqm	
5	Providing and fixing M.S. hollow door frame of size 100X50X2.20mm including hinges, bead and if required angle threshold of mild steel angle and applying a coat of approved steel primer as directed by E/I.	8.20	Rmt	
6	Painting two coats with Supirior synthetic enamel paint one coat primer new Surface including supply of labour material t&p etc.complete.	5.00	Sqm	
7	P/F Fly proof stainless steel grade 304 wire gauge with 0.5 mm dia wire and 1.4mm wide aperture with M.S. flat 15X3mm and nuts and bolts complete.	1.01	Sqm	
8	Scraping old white or colour wash etc.including disposal of refuse material as directed by Engineer-in-charge.	172.06	Sqm	
9	Providing and laying cement based white putty of average thickness 0.60mm of approved brand and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	172.06	Sqm	
10	Distempering with oil bound distemper two coat of approved brand old Surface to give an even shade including all material , labour T&P etc. complete.	285.96	Sqm	
11	Painting two coats with Superior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	57.14	Sqm	
12	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with 4mm thick glass panes.	0.26	Sqm	
13	S/f of Descon make or equivalent Solid PVC door frames of 65mm x 46mm & shutter 25mm (Solid thick with ribs) Grey/Dark Grey/Black thick mode of Foam PVC sheet including Aluminum hardware, sliding bolt, Handles & hing.	1.64	Sqm	
14	S/f C.P health faucet with c.p lead 1.5 m.for appd. Quality.	01	Nos	
15	S/F PVC waste pipe 32mm dia 600m long.	02	Nos	

किंग जार्ज चिकित्सा विश्वविद्यालय उ0प्र0, लखनऊ– 226003
निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 बेवसाइट : www.kgmcindia.edu.

पत्रांक: S802/m-10/2022 दिनांक: 09/09/22

16	Providing welding machine with welder for Repair of old M.S doors and windows.	01	No.	
17	Providing carpanter with helper for Repair of old doors and windows.	01	No.	
18	Providing labour (unskilled) for cleaning of site and collecting malwa	04	Nos	

Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

(Dinesh Kumar Raj)
Executive Engineer

JE A.E

No. S802/m-10/2022 / of DT. dt. 09/09/22

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Faculty Incharge, Website Administratiion Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 09/09/2022 To 16/09/2022
3. Sri Suresh Kumar, Assistant Engineer, Works deptt. K.G.M.U.U.P.Lucknow
4. Sri T.C Yadav, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow
5. Notice Board.

(Dinesh Kumar Raj)
Executive Engineer

JE A.E