



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003  
निर्माण विभाग

R. 25-8-2020

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: 3785/110

**QUOTATION NOTICE**

दिनांक: 25/08/2020

To,

M/s.....

The sealed quotations are invited for Repairing & painting work of Dialysis unit and seminar room at ICU medicine building. The details of quotation notice can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated 22/09/2020

Details of work as given below:-

S.No.	Particulars	Quantity	Unit	Rate
1.	Dismantling of old door / windows chaukhats with hold fast & including stacking of dismantled material directed by the engineer incharge.	1.80	Sqm.	
2.	Dismantling old tiles including disposal of refuse as directed by Engineer-in-charge .	1.56	Sqm.	
3.	Dismantling wooden boardings in lining of walls and partitions, up to 10 mm thick.	22.50	Sqm.	
4.	Dismantling G.I. pipes (external work) upto 40mm dia including excavation and refilling trenches after taking out the pipes.	12.41	Rmt.	
5.	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	1.35	Sqm.	
6.	P/L kajaria or equivalent floor tiles 200x300mm with water absorption less then 0.08% and conforming to IS: 15622 of approved make in all colours and sheds , laid on 20mm thick cement mortar in 1:4 cement coarse sand including grouting of jointes with white cement and matching pigment.	4.09	Sqm.	
7.	Scraping old white or colour wash etc. including disposal of refuse material as directed by Engineer-in-charge.	138.23	Sqm.	
8.	Providing and laying cement based white putty of average thickness 0.60mm of approved brand and manufacture, over the old painted wall surface to prepare the surface even and smooth complete.	138.23	Sqm.	
9.	Providing and laying white cement based putty of average thickness 1mm of approved brand on new plastered surface to prepare the surface even and smooth complete.	1.35	Sqm.	
10.	Distempering with oil bound distemper two coat of approved brand on old Surface to give an even shade including all material , labour T&P etc. complete.	515.63	Sqm.	
11.	Painting two coats with Supirior synthetic enamel paint in old Surface including supply of labour material t&p etc. complete.	170.39	Sqm.	
12.	S/f of anodised aluminum partly fixed and partly openable window with aluminum section 4x1-3/4x2" window panel and 5mm thick plain glass including all. Labour, material, t&p etc.	1.80	Sqm.	
13.	Providing & fixing Stainless steel fly proof wire gauze to windows, clerestory windows & doors with M.S. Flat 15x3 mm and nuts & bolts complete.	18.26	Sqm.	
14.	S/F plywood 6mm thick ISI mark.	5.76	Sqm.	
15.	Providing & fixing glass panes 4 mm thick with putty and glazing clips in steel doors, windows, clerestory windows, all complete.	0.96	Sqm.	

Sand Kumar



# किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ- 226003 निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 फैक्स : 0522&225753 वेबसाइट : www.kgmcindia.edu.

पत्रांक: .....

दिनांक: .....

16.	S/F PVC waste pipe 32mm dia 600m long.	03	Nos.	
17.	Labour Charge for Repairing of old Aluminium doors.	4.14	Sqm.	
18.	Providing welder with welding machine for fabrication.	01	No.	
19.	Providing Plumber with helper for repairing of old fitting.	01	No.	
20.	Providing Carpenter with helper for repairing of old door/window.	01	No.	
21.	Providing labour for cleaning of site and collecting malwa.	04	Nos.	

### Terms & Conditions

1. G.S.T and labour cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotations are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

(Dinesh Kumar Raj)  
Executive Engineer

8786-90/M/10  
No. .... of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.
2. Dr. Sandeep Bhattacharya, Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from date 25/08/2020  
i. To 22/09/2020
3. Sri Suresh Kumar, Assistant Engineer, Works deptt. K.G.M.U. U.P. Lucknow
4. Sri T.C Yadav, Junior Engineer, Works deptt. K.G.M.U. U.P. Lucknow
5. Notice Board.

(Dinesh Kumar Raj)  
Executive Engineer