किंग जार्ज चिकित्सा विश्वविद्यालय उ0प्र0, लखनऊ-226003

(विद्युत/यांत्रिक)विभाग,

गॉधी स्मारक एवं सम्बद्ध चिकित्सालय,

पत्रांक 1048/....नोटिस/ई0ई0(ई0/एम0)/26 दिनाँक 16/10/...2026

Quotation Notice

The sealed Quotations are invited for **Replacement of Defective Automatic Transfer Switch 630Amp. Generator Panel of 320 KVA Cummins make DG Set No 02 installed at Gandhi ward, KGMU Lucknow.** The details of quotation can be seen at website:- www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations(For the purpose for estimated Cost of Work) to the office of undersigned by post or by hand duly marked on the envelope the number and date of this notice latest by dated..19/10/26.....

S.No.	Particulars	Qty	Rate	Amount
1.	Supply and Fixing of automatic Transfer switch ATc 52/4 pole, Voltage: AC415/50Hz, PC- Class ICM 26KAIQ. 120KA with panel and connection the same in existing busbar complete job.	01 No.		
2.	Supply, Fabrication & fixing of additional terminal for automatic transfer switch suitable for 630Amp. ATS switch with making connection of incoming for ATS switch with help of nut-bolt & washer complete job.	04 Nos		
3.	Dismantling Charges for defective ATS switch 630Amp. Capacity from existing Generator Panel with disconnection of incoming & outgoing busbar panel with testing, mega-ring & commissioning the same complete job.	01 Job		
			Total	

Term & conditions

1. All the work shall be completed within the given time period as per work order.
2. G.S.T. paid as per applicable.
3. Quantity can be increase of Decrease as per requirements.
4. Conditional quotaion are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

Executive Engineer(E/M)
King George's Medical University
Lucknow.

Section No.1048/EE(E/M).....**Notice/E.E(E/M)/26 .of Date**....16/10/2026..... OC Dinesh

Copy for information and necessary action to :-

1. Faculty incharge, Website Administration, Data Center , P.H.I Bhawan, KGMU for uploading the Quatation Notice in KGMU. Website from Date.16/10/26.....to..19/10/26.....

Executive Engineer(E/M)
A OC Dinesh