

**WORKS DEPARTMENT, KING GEORGE'S MEDICAL UNIVERSITY
U.P, LUCKNOW**

of dt. 09/01/2020

No. 6767/M10 **Quotation Notice**

Sub:- Misc Civil Renovation Toilet work, Deptt. of P.R.O. Office Main Building, KGMU, U.P., Lucknow

Dear sir,

Please quote your rates for the above work as per specifications given below. The sealed quotations should reach to undersigned duly marked on the envelope the number and date of this notice latest by 3:30 P.m on dated. 16/01/2020

Sl.No	Particular	Quantity	Unit	Rates
1	Dismantling Brick work or stone work in lime are cement mortar and including stacking of material as directed by the Engineer-in-charge complete etc.	0.78	Cum	
2	Dismantling of Existing old plaster	36.20	Sqm	
3	Dismantling of old unserviceable flooring/Kota stone	12.35	Sqm	
4	Providing and laying Vitrified tiles in floor with different sized(thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS:15622, of approved brand & manufacturer, in all colours and shade laid with cement based high ploymer modified quick set tile adhesive(water based) conforming to IS:15477, in average 6mm. thickness, including grouting of joints (Payment for grouting of joints to be made separately) (Size of tile 600x600mm)	12.35	Sqm	
5	P/L Kajaria or equivalent wall tiles 300x600mm. with water absorption less than 0.08% and conforming to IS:15622 of approved make in all colours and sheds, lied on 20mm. thick cement mortar in 1:4 cement and coarse send including grouting of joints with white cement matching pigment.	36.20	Sqm	
6	S/F anodized aluminium door/window 2mm thick fully glazed made aluminium door tube size 83.50x44.65mm as vertical member 114.00x44.65mm with 5mm thick glass.	4.38	Sqm	
7	Scraping of colour white wash old surface.	13.10	Sqm	
8	P/L of Birla white putty for making good smooth surface.	13.10	Sqm	
9	Oil bound distemper in two coat.	7.30	Sqm	
10	Enamel painting in two coat	9.35	Sqm	
11	S/f orrisa pan 580mm dia.	01	Nos	
12	S/f of 10 lit P.V.C. low down cistern for appd. quality in completed.	01	No	
13	S/f of Urinal Pot	01	No	
14	S/f wash basin 22"x16" with PVC connection, pillar cock and bracket complete.	01	Nos	

Terms & Condition

1. The quotation should be accepted by Registered Contractor of KGMU.
2. The rates should be quoted excluding G.S.T. & Labuor Cess.
3. The work will completed within given time in the work order.
4. The quotation should be reached by Registered post upto date mentioned in quotation

Yours Faithfully

Ram Velas Verma
(Ram Velas Verma)
Executive Engineer

No. 6768-73/M10

Date.....

Copy for Information and necessary action to:

1. Registrar, K.G.M.U, U.P. Lucknow.
2. Finance Officer, K.G.M.U, U.P. Lucknow.
3. Chief Medical Superintendent, K.G.M.U, U.P. Lucknow.
4. Dr. Sandeep Bhattacharya, Website Administration Finance & Contact, P.H.I Bhawan, K.G.M.U. for uploading the quotation Notice in K.G.M.U.
5. Assistant Engineer, Works deptt. K.G.M.U, U.P. Lucknow.
6. Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow.
7. Notice Board.

Ram Velas Verma
(Ram Velas Verma)