



किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ-226003  
कार्यालय अधिशासी अभियंता (विद्युत/यॉन्त्रिक)

पत्रांक 1427/EE (E/M)

दिनांक 12/10/2023

**Urgent Quotation Notice**

Sub: - Rewiring & providing of light point, fresh air point, power point for Pantry at Hon'ble V.C. Office, KGMU, Lucknow.

Kindly submit your Quotation/Estimate for providing the following work in sealed envelope to the undersigned in the interest of patient care/institution within 3 days from the date of dispatch.

S.No.	Particulars	Qty.	Rate In each	Amount In Rs.
1	Wiring point for light with 1.5mm single core copper wire. As per PS No 131C+187A.	05 Nos.		
2	Wiring point for Fan with 1.5mm single core copper wire as per PS No 133C+187A.	04 Nos.		
3	S/F of 10A Plug point Modular with 1.5mm single core copper wire. As per PS No 134C+187C.	07 Nos.		
4	S/F of power plug with 20A/250V flush type Modular type switch & 5 pin 20A 250V universal modular socket. As per PS No 1139A.	06 Nos.		
5	S/F of modular board 12 module. As per PS No 1152 F.	04 Nos.		
6	S/F of modular cover plate 12 module.	04 Nos.		
7	S/F of modular board 6 module. As per PS No 1152 D.	01 No.		
8	S/F of modular cover plate 6 module.	01 No.		
9	S/F of 01x20 watt LED fittings complete in all respect.	02 Nos.		
10	S/F of recess/ surface mounting round 34 to 32 watt LED Down lighter. As per PS No 1405 Catt AAA.	01 No.		
11	S/F of 36 watt to 46 watt indoor recess mounting LED square fitting for armstrong ceiling light. As per PS No 1406 Catt AAA	01 No.		
12	S/F of wall fan oscillating type 400mm	02 Nos.		
13	S/F of fresh air fan.	02 Nos.		
14	S/F of Blanking plate as per PS No 1034 (B)	08 Nos.		
15	S/F of MCB 6 to 32 amp. As per PS No 1002	06 Nos.		
16	S/F of DP MCB 63 amp. As per PS No 1011	01 No.		
17	S/F of 8 way SPN DB DD as per PS No 1024 S	01 No.		
18	S/F of submain 2x 2.5 sq.mm with multistrand single core copper wire. as per PS No 1304 C	25 Mtrs.		
19	S/F of submain 2x 4 sq.mm with multistrand single core copper wire. as per PS No 216 C.	40 Mtrs.		
20	S/L of cable 10sq.mm. 2 core armoured as per PS No 501 (b)	28 Mtrs.		
21	S/F of extension board having 1x5 and 1x15 amp switch socket with 3 core lead & plug top 3 pin complete with modular board and plate.	01 No.		
22	Dismantling charges of old & unserviceable cable wiring, switch, board, DB etc complete for restoration of Electric supply.	01 No.		
Total				

**Terms & Conditions:-**

1. G.S.T. : As Applicable.
2. All the works shall be completed within the given time period as per work order.
3. Quantity can be increase or decrease as per requirements.
4. All the works shall be carried out as per PWD specifications.
5. Firm should fill the A.R. Rate other than schedule Rate.
6. Contractor having experience in electrical department KGMU Lucknow can quote their rates.

Your Faithfully

Executive Engineer (Electrical)  
K.G.M.U.U.P., LUCKNOW

No.....of DT.....

Copy for information and necessary action to:-

1. Dr. Richa Khanna, Faculty In charge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU. Website from.....
2. Notice board.

Executive Engineer (Electrical)  
K.G.M.U.U.P., LUCKNOW