

किंग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ - 226003 निर्माण विभाग

फोन (कुलसचिव कार्यालय) : 0522-2257540 Email : eng.civil@kgmcindia.edu

	1123/011
पत्रांकः	435/M

To,

QUOTATION NOTICE

दिनांक:
allact
20/00/24

	,																				
M																					
		 • • •		*	* *	*	 											 		4	
		 	 				 	٠,				٠.			*	٠	 ٠	* 1		(8)	

The sealed quotations are invited for providing and fixing rain water pipe and casting of R.C.C cover and other miscellaneous work of new boys hostel at T.G. campus from the registered contractor of KGMU. The detail of quotation notice can be seen at website www.kgmu.org and on the Notice board of the office of undersigned Interested parties may

Sl.No.	the work as given below-	Qty.	Unit	Rate
1	Dismantling old damaged G.I. pipes 25mm dia internal work including stacking of dismantled pipes as per direction of E/I.	32.50	Rmt.	
2	Dismantling of brick work in cement mortar including stacking of material as directed by Engineer-in-charge.	0.61	Cum.	
3	P/L PCC 1:6:12 cement, fine sand & 40mm brick ballast.	0.24	Cum.	1
4	P/L R.C.C Cover in 1:1.5:3 cement, coarse sand and stone aggregate.	0.12	Cum.	
5	M-150 class 120mm thick brick work in 1:3 cement & coarse sand in super structure including supply of all materials, labours and T&P etc.for proper completion of the work.	9.72	Sqm.	
6	M-150 Class 230mm thick brick work in 1;4 cement coarse sand in super structure including supply of all materials, labours and T&P etc.for proper completion of the work.	0.61	Cum.	
7	P/L 12mm cement plaster in 1:6 on wall with cement and coarse sand including supply of all material labour and T&p etc. for proper completion of the work.	5.28	Sqm.	
8	15mm cement plaster 1:3 cement coarse sand finishing with a floating coat of neat cement.	12.15	Sqm.	
9	Applying one coat white cement on new surface.	5.28	Sqm.	
10	Providing and laying white cement based putty of average thickness Imm of approved brand on new surface.	5.28	Sqm.	
11	Application of two coats apex Ultima paint on outer surface including supply of all materials, labours and T&P etc. for proper completion of the work.	5.28	Sqm.	
12	Mild steel work for reinforment in plain concrete work including cutting bending and binding and also including binding wire.	18.41	Kg.	
13	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies. M.S clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-incharge.	33.00	Sqm.	
14	Providing and fixing G.I pipes 25mm dia complete with G.I fittings	32.50	Rmt.	





किं

ग जार्ज चिकित्सा विश्वविद्यालय उ०प्र०, लखनऊ— 226003 निर्माण विभाग

फोन (कुलसचिव कार्यालय): 0522-2257540 Email: eng.civil@kgmcindia.edu

15	P/F PVC Pipe 100mm dia 6kg pressure ISI make.	36.10	Rmt.
16	P/F PVC plain bend 100mm dia.	03	Nos.
17	P/F of M.S holder bat clamp for pipe 100mm dia.	12	Nos.
18	P/F Brass ball valve 25mm dia. of approved quality, high or low pressure, with plastic floats complete.	05	Nos.
19	Providing labour for cleaning of site and collecting malwa.	05	Nos.

Terms & Conditions.

- 1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
- 2. The work will be completed within given time.
- 3. Quantity can be increase or decrease as per requirements.
- 4. Conditional quotations are liable to be rejected.
- 5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours faithfully

(Suresh Kumar) Executive Engineer

of DT.

Copy for information and necessary action to:-

1. Registrar, King George's Medical University U.P, Lucknow.

Sri Abhishek Sharma, Junior Engineer, Works deptt. K.G.M.U.U.P.Lucknow

Notice Board.

(Suresh Kumar) **Executive Engineer**