

(Civil Section)

King George's Medical University

P: 02-03-2021

(Civil Section)

King George's Medical University Uttar Pradesh,
Lucknow.

P: 02-03-2021

578

No. 1977-82/M/10

of date 01/03/2021

QUOTATION NOTICE

To,

M/s.....

The sealed quotation are invited for **Misc. Civil work including water Supply & sanitary work in Maha Maya Hostel at K.G.M.U. U.P., Lucknow.** from the registered contractor of K.G.M.U. The Detail of quotation can be seen at website www.kgmcindia.edu and on the Notice board of the office of undersigned. Interested parties may submit their quotations to the office of undersigned by registered post or by hand duly marked on the envelope the number and date of this notice latest by dated. 01/03/2021

Details of the work as given below-

S.N.	Particular	Quantity	Unit	Rates
1.	P/F Appd. Quality steel sink without drainage board size 1040x510x200mm with bracket waste jali waste pipe complete.	4.00	No	
2.	S/F of C.I. P Trap 100mm. dia	1.00	No	
3.	S/F of Orissa pan 580mm dia with C.I. trap.	1.00	Nos.	
4.	P/L of 20mm approved quality of Red Lakha granite slab/stone in rise of steps skirting dodo walls and pillars, laid of 10mm thick base jointing with cement slurry including colouring all labour material T&P etc. upto the proper competition of the work as per direction of Engineer-in-charge.	3.42	Sqm	
5.	P/L Kajaria or equivalent wall tiles 300x600mm. with water absorption less than 0.08% and conforming to IS:15622 of approved make in all colours and sheds, lied on 20mm. thick cement mortar in 1:4 cement and coarse send including grouting of joints with white cement matching	2.95	Sqm	
6.	P/F Anodized aluminum work for doors, windows and ventilators with extruded built up standard tabular section/ appropriate Z section and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia. and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required with rubber/neoprene gasket etc.	54.10	Kg.	
7.	S/f Anodized Aluminium grill with stainless steel wire gauge including all material labours T&P complete.	14.98	Sqm	
8.	Providing and fixing of C.P. short body bib cock 15mm dia make of plumber.	4.00	Nos.	
9.	Providing labour for cleaning of site and collecting malwa.	8.00	Nos.	

Terms & Conditions.

1. G.S.T & Labour Cess shall be paid or deducted as per rules applicable.
2. The work will be completed within given time.
3. Quantity can be increase or decrease as per requirements.
4. Conditional quotation are liable to be rejected.
5. The undersigned reserves the right to reject quotations in part or whole without assigning any reason.

Yours Faithfully

Ram Velas Verma
(Ram Velas Verma)
Executive Engineer

No. 1977-82/M/10

Date.....

Copy for Information and necessary action to:

1. Registrar, K.G.M.U, U.P. Lucknow
2. Finance Officer, K.G.M.U, U.P. Lucknow
3. Warden, Maha Maya Hostel, K.G.M.U, U.P. Lucknow
4. Dr. Richa khanna, Faculty Incharge, Website Administration Data Center, PHI Bhawan, KGMU for uploading the quotation Notice in KGMU, Website.
5. Assistant Engineer, Works deptt. K.G.M.U, U.P. Lucknow
6. Junior Engineer, Works deptt. K.G.M.U, U.P. Lucknow
7. Notice Board.

Ram Velas Verma
(Ram Velas Verma)
Executive Engineer